

State of Kansas



15.009.19443.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
300 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 8 1967
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Richard B. Scheck of Drlg.-Prod. Pipe & Supply, INCs this date requested permission to plug the following described well:

Mr. Richard B. Scheck guarantees payment of the plugging fee.

Operator's full Name: Drillers-Producers Pipe & Supply Co., Inc.

Complete Address: Box 368, Great Bend, Kansas 67530

Lease Name: Dirks Well No. # 1

Location: NE NE SW Sec. 6 Twp. 20 Rge. 14 (E)(W)W

County Barton Total Depth 3840 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Albert Unruh was instructed to plug the well as follows:

- 8 5/8" 826' Cwc.
- Sanded hole back to 3450' & dumped 4 sax cement with dump bailer.
- Pulled pipe. Mudded hole to 400', set 25' rock bridge, & displaced
- 5 yds. ready-mix cement, cementing from 375' to base of cellar.

Very truly yours,

Don Truman
Conservation Division Agent