

1 080401

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,187.0066

SE NW NE, SEC. 21, T 20 S, R 18 (W)K

4290 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name Cox "A" Well # 1

Operator: Frontier Oil Company

County Pawnee 124.33

Name & Address 1720 Kansas State Bank Building

Well Total Depth 4133 (Arbuckle) feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 219

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Frontier Oil Company License Number 5140

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 9:00 am Day: 11 Month: July Year: 19 85

Plugging proposal received from Terry Piester

(company name) Frontier (phone) 316-263-1201

Elevation 2202'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1354'

1st plug at 1354' with 50 sx cement

2nd plug at 787' with 70 sx cement

3rd plug at 240' with 40 sx cement

solid bridge

4th plug hulls - plug at 60' -- cement to surface with 20 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by J. A. Miller (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:30 am Day: 11 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1354' with 50 sx cement, 2nd plug at 787' with 70 sx

cement, 3rd plug at 240' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 60' -- cement to surface with 20 sx cement, 6th plug to circulate rat hole with 15 sx

cement.

RECEIVED STATE CORPORATION COMMISSION

PL

JUL 22 1985

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use reverse side of this form.)
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 7-24-85

INV. NO. 9090

Signed J. A. Miller (TECHNICIAN)