

Kansas Corporation Commission
District Plugging Report

API Well Number: 15-019-19134-00-00
 Spot: SE/NE/SW Sec 25 Twp 34 S Rng 11 E / W
1591 Feet from N / S Line of Section
3173 Feet from E / W Line of Section
 GPS: Lat: 37.058624 Long: -96.156187 Date: 7/25/17
 Lease Name: McNown (McNown) Well #: MCN 06 (6)
 County: Chautauqua Total Vertical Depth: 1100 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>KANSAS CORPORATION COMMISSION</u>	<u>SURF - Casing</u>	<u>7.000</u>			
Address 1: <u>266 N MAIN STE 220</u>	<u>T1 - Tubing 1</u>	<u>4.000</u>			
Address 2: _____	<u>T2 - Tubing 2</u>	<u>2.000</u>			
City: <u>WICHITA</u>					
State: <u>KS</u> Zip Code: <u>67202</u>					

Well Type: OG - Oil & Gas (oil) UIC Docket No.: _____ Date/Time to Plug: 8/10/17 / _____
 Plug Co License No.: 6372 Plug Co. Name: Splane Pulling & Roustabout Service Inc.
 Proposal Revd from: Keith Splane Company Name: _____ Phone: (620) 433-0448

Proposed Plugging Report: **CLEAN OUT WELLS TO BOTTOM. PUMP FULL OF PORTLAND CEMENT, INSIDE AND OUTSIDE OF CASING. IF CEMENT IS PRESENT IN THE ANNULUS, CASING SHOULD BE PERFORATED IN AT LEAST 2 INTERVALS, UNLESS WELL IS DOCUMENTED AS ALT. 2 COMPLETION.**

Plugging Proposal Received By: Tom Bilyeu Witness Type: PART - Partial
 Date/Time Plugging Completed: 8/10/17 / _____ KCC Agent: Tom Bilyeu

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
CLEARED TREES AROUND THE WELL. TRIED TO PULL 2" AND COULD NOT. RAN BIT IN 2" TO 600' AND PERFED. RAN 1" TO 1100' AND PUMPED 161 SACKS OF CEMENT. GOT GOOD CIRCULATION UP ALL STRINGS OF PIPE. THE LOCATION WAS RETORED.		<u>500</u>		
		<u>350</u>		
		<u>150</u>		

Remarks: Contract#42399; Control#20170009-006; Nad 83; Gps by Tom, Tony

Plugged Thru: _____ Plugged Due to Compliance Issue: Yes No

District: 03
 RECEIVED KANSAS CORPORATION COMMISSION
 OCT 09 2017
 WICHITA, KS
 10-9-2017
 Form: District Plugging Report - _____