

6 061411  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1-22-88 219  
API NUMBER 15-009.24187.000'0  
SW, SEC. 1, T 20 S, R 14 W/E  
990 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4087  
Operator: Williamson Drlg. Inc.  
Name & Address: 5501 Navajo  
Great Bend, Ks. 67530

Lease Name Merten Well # 1  
County Barton 115.54  
Well Total Depth 3555 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 426'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347, Chase, Ks. 67524

Company to plug at: Hour: 8:30 AM Day: 22 Month: Jan. Year: 19 88

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2457

were: Order 175 sk 65/35 pozmix 10% gel 2% Econolite, 5 sk hulls

Plugging Proposal Received by Gilbert Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30PM Day: 22 Month: Jan Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 426' with 275 sks. 5 1/2" set at 3528' with 175 sks.

Top perf. at 3352' plugged bottom with sand and 5 sks cement

to 3300' Shot pipe 4 time and recovered 2400'. Pumped in 5 1/2". Spotted

cement from 1000' to surface, Hooked on to 8 5/8" and pumped cement

w/300 P.S.I. used 175 sk cement total.

FEB 05 1988 2-5-1988

Remarks: By Allied  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 2-5-88  
INV. NO. 19778

Signed Gilbert Scheck  
(TECHNICIAN)