

11-18-87

To: 6 061372  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-009.23381.0001  
NW, SEC. 17, T 20 S, R 14 (W/E)  
3630 feet from S section line  
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5591

Lease Name Schmidt Well # 2

Operator: Westech Energy Co. Inc.

County Barton 119.60

Name & Address Box 949

Well Total Depth 3680 feet

Great Bend, Ks. 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 857

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering Inc. License Number 5111

Address Box 698 Great Bend, Kansas 67530

Company to plug at: Hour: 10:00AM Day: 18 Month: Nov Year: 19 87

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering Inc. (phone) 316-792-2506

were: Order 100 sks 65/35 Pozmix 10% Gel 2% Econolite 5 sks Hulls.

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:15PM Day: 18 Month: Nov. Year: 19 87

ACTUAL PLUGGING REPORT 8 5/8" set at 857' w/450 sks. 5 1/2" set at 3679 w/200 sks.

Top perf at 3605'. Plugged bottom w/sand and 5 sks cement to 3550'. Shot pipe 1 time and

recovered 2701'. Pumped in 8 5/8". 5 sks Hulls. 100 sks cement w/700 Psi. RECEIVED

STATE CORPORATION COMMISSION

NOV 30 1987

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: By Allied.  
(If additional description is necessary, use BACK of this form.)

11-30-1987

I hereby ~~authorize~~ observe this plugging.

DATE 12-7-87

Signed Gilbert G. Scheck  
(TECHNICIAN)

INV. NO. 19154

Gilbert G. Scheck