

4-060394

4-15

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-009-23,522-0000

NW NW SW /4 SEC. 30, 20 S, 14 W  
2310 feet from S section line  
4950 feet from E section line

Operator license# 5591 Lease Unruh well # 1-30

Operator: Westech Energy Co., Inc. County Barton

Address: P.O. Box 949 Well total depth 3680 feet  
Great Bend, Kansas 67530 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 870 feet

119.60

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Great Bend Casing Pullers, Inc. License# 4635

Address: P.O. Box 251 - Great Bend, Kansas 67530

Company to plug at: Hour: A.M. Day: 15 Month: April Year: 93

Plugging proposal received from: Gary Burke

Company: Great Bend Casing Pullers, Inc. Phone: 316-792-5653

Were: Order 275 sxs. 65/35 posmix - 10% gel. and hulls.  
Operator and plugging contractor contacted office prior to plugging to  
review plugging methods. Ran into long delays due to wet winter  
inaccessibility to well site.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 11:45A.M., Day: 15, Month: April, Year: 93

Actual plugging report: 8 5/8" to 870'. 5 1/2" to 3678'. Sand back  
3625' and spot 5 sxs. cement with bailer. Shot twice and recovered 2701'  
of casing. Tied onto surface pipe and pumped 275 sxs. cement with  
500# hulls. Max. 700#. S.I.P. 300#. Calculated volume to 2000'+.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO  
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING X. Elevation: 1907

RECEIVED STATE CORPORATION COMMISSION

MAY 18 1993

CONSERVATION DIVISION  
Wichita, Kansas

I did not observe the plugging.

[Signature]

DN (agent)

INVOICED

DATE 5-18-93

INV. NO. 37744