

6 061830

4-17

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009.23596.0001

NE NW NE, SEC. 30, T. 20 S, R. 14 W/E

4950 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

6050

Operator License #

Lease Name Smith 1 Well # 1-30

Operator: Kelso Casing Pulling Inc.

County Barton 130.91

Name & Address: Box 347 Chase, Ks. 67524

Well Total Depth 4028 feet

BOGER BROTHERS DRILLING

Conductor Pipe: Size feet

P O BOX 723
GREAT BEND KS 67530

Surface Casing: Size 8 5/8 feet

Abandoned Oil Well Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 1:00 PM Day: 17 Month: April Year: 19 89

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 306-938-2943

were: Order 200' sks 60/40 Poz 8% Cel 5 sks Hulls.

STATE CORPORATION COMMISSION
MAY 10 1989
Wichita, Kansas

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30 PM Day: 17 Month: April Year: 19 89

ACTUAL PLUGGING REPORT 8 5/8" set at 864' w/cwc. 5 1/2" set at 3706' w/150

sks. Top perf at 3706'. Plugged bottom w/sand and 5 sks cement to 3650'. Shot pipe two times and recovered 2420'. Pumped in 8 5/8" 25 sks cement followed w/5 sks Hulls in 175 sks cement w/300 psi.

Remarks: By Allied

(If additional description is necessary, use BACK of this form.)

INVOICED
(old version) Observe this plugging.

DATE 5-11-89

Signed [Signature] (TECHNICIAN)

INV. NO. 24780

JUL 11 1989

Gilbert G. Scheck CP-2/3 Rev. 01-84