

4-060393

4-15

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-009-01,013.0001

SW SW NW /4 SEC. 30, 20 S, 14 W  
2970 feet from S section line  
4950 feet from E section line

Operator license# 5591 Lease Biermann OWWO well # 1

Operator: Westech Energy Co., Inc. County Barton

Address: P.O. Box 949 Well total depth 3680 feet  
Great Bend, Kansas 67530 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 868 feet

119.60

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Great Bend Casing Pullers, Inc. License# 4635

Address: P.O. Box 251 - Great Bend, Kansas 67530

Company to plug at: Hour: A.M. Day: 15 Month: April Year: 93

Plugging proposal received from: Gary Burke

Company: Great Bend Casing Pullers, Inc. Phone: 316-792-5653

Were: Order 275 sxs. 65/35 posmix - 10% gel. and hulls.  
Operator and plugging contractor contacted office prior to plugging to  
review plugging methods. Ran into long delays due to wet winter  
inaccessibility to well site.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 10:00A.M., Day: 15, Month: April, Year: 93

Actual plugging report: 8 5/8" to 868'. 5 1/2" to 3680'. Sand back  
3575' and spot 5 sxs. cement with bailer. Shot three times and pulled  
2351' casing. Tied onto surface pipe and pumped 275 sxs. cement with  
500# hulls. Max. 600#. S.I.P. 200#. Calculated volume to 2000+.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Allied Cementing. MAY 18 1993  
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO  
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X  
Plugged through TUBING, CASING X. Elevation: 1908 GL  
CONSERVATION DIVISION  
Wichita, Kansas

I did [ ] / did not [ X ] observe the plugging.

*[Handwritten signatures]*  
(agent)

INVOICED

DATE 5-18-93

INV. NO. 37743