

4-060392

4-15

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-24,053.0000

SW NE SE /4 SEC. 30 , 20 S, 14 W
1650 feet from S section line
990 feet from E section line

Operator license# 5591 Lease Weathers well # B-1
Operator: Westech Energy Co., Inc. County Barton

Address: P.O. Box 949 Well total depth 3680 feet
Great Bend, Kansas 67530 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 868 feet

119.60

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Great Bend Casing Pullers, Inc. License# 4635

Address: P.O. Box 251 - Great Bend, Kansas 67530

Company to plug at: Hour: P.M. Day: 15 Month: April Year: 93

Plugging proposal received from: Gary Burke

Company: Great Bend Casing Pullers, Inc. Phone: 316-793-9711

Were: Order 275 sxs. 65/35 posmix - 10% gel. and hulls.
Operator and plugging contractor contacted office prior to plugging to
review plugging methods. Ran into long delays due to wet winter
inaccessibility to well site.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:45P.M., Day: 15, Month: April, Year: 93

Actual plugging report: 8 5/8" to 868'. 5 1/2" to 3675'. Sand back
3580' and spot 5 sxs. cement with bailer. Shot twice and recovered 2623'
of casing. Tied onto surface pipe and pumped 275 sxs. 65/35 posmix -
10% gel. and 500# hulls. Max. 800#. S.I.P. 300#. Calculated fill to
2000'+. Calculated volume to 2000'+.

RECEIVED
STATE CORPORATION COMMISSION

MAY 18 1993

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 1907 GL

I did or did not observe the plugging.

[Signature] *[Signature]*

[Signature] (agent)

Form CP-2/3

INVOICED

DATE 5-18-93

INV. NO. 37742