

15.009.23697.0000

12-16-87

6 061387

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 009-23,697

SE, SEC. 30, T 20 S, R 14 W/E

1650 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5591

Lease Name Weathers Well # 1-30

Operator: Wes Tech Energy Co Inc.

County Barton 119.60

Name & Address Box 949

Well Total Depth 3680 feet

Great Bend, Ks. 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 870

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering Inc., License Number 5111

Address Box 949 Great Bend, Ks. 67530

Company to plug at: Hour: 9:00AM Day: 16 Month: Dec Year: 19 87

Plugging proposal received from D. B. Pullie

(company name) Rockhold Engineering Inc. (phone) 316-792-2506

were: Order 125 sks 65/35 Pozmix 10% Gel 2% Econolite 5 sks Hulls.

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:45PM Day: 16 Month: Dec Year: 19 87

ACTUAL PLUGGING REPORT 8 5/8" set at 870' w/450 sks. 5 1/2" set at 3675' w/125 sks.

Top perf at 3631'. Plugged bottom w/sand and 5 sks cement to 3575'. Shot pipe one time and recovered 2851'. Pumped in 8 5/8". 25 sks cement w/5 sks Hulls in 100 sks cement w/650 Psi.

12-29-87 DEC 29 1987

Remarks: By B. J. Titan (If additional description is necessary, use BACK of this form.)

INVOICED (delivered to customer observe this plugging.)

DATE 1-17-88

Signed Gilbert G. Scheck (TECHNICIAN)

INV. NO. 19425

Gilbert G. Scheck FORM CP-2/3 Rev. 01-84

LR