

To: 6 090403
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-30
API NUMBER 15- 15.009-23,947.0000

NW, SEC. 29, T 20 S, R 14 W/E
3284 feet from S section line
4636 feet from E section line

TECHNICIAN'S PLUGGING REPORT
5591
Operator License # _____

Lease Name Ohnmacht Well # 3
County Barton 119.60

Operator: Westech Energy Co., Inc.
Name & Address Box 949
Great Bend, Ks. 67530

RECEIVED
STATE CORPORATION COMMISSION

Well Total Depth 3680 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 866

Abandoned Oil Well x Gas Well _____
Other well as hereinafter indicated _____

RECEIVED
CONSERVATION DIVISION
WICHITA, KANSAS
JAN 18 1989

Plugging Contractor Allied Cementing Co., Inc. License Number _____

Address Great Bend, Ks.

Company to plug at: Hour: 10:30AM Day: 30 Month: Nov Year: 19 88

Plugging proposal received from James Rockhold

(company name) Rockhold Engineering Inc. (phone) _____

were: 8 5/8" set at 866' w/450 sks. 5 1/2" set at 3679' w/125 sks.

P.B.T.D. 3672'. Bottom plug - sand to 3550' and 5 sks cement. Shot pipe and

recovered 2714' of 5 1/2" casing. Order 200 sks 60/40 Poz 6% Gel and 5 sks Hulls. Perfs

3616' - 3622'

Plugging Proposal Received by Gilbert Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 11:30AM Day: 30 Month: Nov Year: 19 88

ACTUAL PLUGGING REPORT Tie onto 8 5/8" and pump 20 sks.

60/40 Poz 6% Gel followed by 180 sks 60/40 Poz 6% Gel w/5 sks Hulls. Max pressure

500 psi. Shut in pressure 300 psi.

Remarks: Elevation 1905' Anhydrite 860' Arbuckle Yes
(If additional description is necessary, use BACK of this form.)

did not observe this plugging.

INVOICED

DATE 1-19-89

INV. NO. 23669

Signed Edwin A. Schumacher
Edwin A. Schumacher