

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15.809.24187.0000

API NUMBER 3/21/86

LEASE NAME Merten #1

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 1 TWP. 20 RGE. 14W (E) or (W)

COUNTY Barton

Date Well Completed

Plugging Commenced 1/15/88

Plugging Completed 1/18/88

LEASE OPERATOR WILLIAMSON DRILLING, INC.

ADDRESS 5501 Navajo, Great Bend, KS 67530

PHONE# 316 793-8229 OPERATORS LICENSE NO. 4087

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? HAYS DIST #6

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3555'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	426'	None
				5 1/2"	3528'	2406'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Put on control head. Plugged bottom w/sand to 3300' and 5 sacks of cement.

Shot pipe @ 2703', 2611', 2519', & 2406'. Pulled pipe to 900' & Allied Cementing pumped 50 sacks of cement, pulled to 400' and pumped 75 sx and circulated. Pulled rest of pipe and swedged, pumped 50 sx and shut in. **PLUGGING COMPLETE**
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address Box 347, Chase, KS 67524 STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF RICE, ss. FEB 01 1988

MIKE KELSO

(Employee of Operator or Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Bx 347, Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 29 day of January, 1988

James Hoover
 Notary Public

My Commission Expires:

