

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barton County. Sec. 1 Twp. 20S Rge. 14W (E) (W)

Location as "NE/CNWxSWx" or footage from lines SW SE NE

Lease Owner Hellar Drilling Company, Inc. and George Grenyo

Lease Name Caskey Well No. 1

Office Address 1014 Union Center, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 26 19 64

Application for plugging filed June 26 19 64

Application for plugging approved June 26 19 64

Plugging commenced June 26 19 64

Plugging completed June 26 19 64

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Donald Truan, 634 Sunset, Russell, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	401'	8 5/8"	401'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set Plug @ 275'/25 sacks cement
40'/10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

JUL 6 1964

7-6-1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hellar Drilling Company, Inc.

Address 1014 Union Center, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

D. L. Hellar, Pres. of Hellar Drilling Co, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] D.L. Hellar, President

1014 Union Center, Wichita, Kansas 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of July, 19 64

My commission expires March 25, 1968.

Catherine Darcey Notary Public.

DRILLER'S LOG

COMPANY: Hellar Drilling Company, Inc. and George Grenyo
 CONTRACTOR: Hellar Drilling Company, Inc.
 LEASE: #1 Caskey
 LOCATION: SW SE NE 1-20S-14W, Barton County, Kansas
 COMMENCED: June 17, 1964
 COMPLETED: June 26, 1964
 CASING: Set 8 5/8" surface casing @ 401' / 300 sacks cement

0-180	Sand
180-200	Sand & Shells
200-401	Pyrite-Shale-Sand & Red Bed
401-780	Red Bed & shale
780-795	Anhydrite
795-1515	Shale & shells
1515-1755	Shale & Lime - Ft. Riley
1755-1975	Ft. Riley Section
1975-2660	Shale & Lime
2660-3240	Lime & Shale
3240-3284	Lime
3284-3300	L. K.C.
3300-3388	Lime
3388-3403	L. K.C.
3403-3508	Lime & shale
3508-3542	Arbuckle
3542	Rotary Total Depth

Dry and Abandoned

RECEIVED
 STATE CORPORATION
 JUL 6 1964
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Caskey, located in SW SE NE 1-20S-14W, Barton County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 1st day of July, 1964.

My Commission Expires:
 March 25, 1968.

Catherine Darcey
 Notary Public - Catherine Darcey