

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
1 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

API NUMBER 15-009-21876-0001

LEASE NAME Bush

WELL NUMBER #2

330 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 1 TWP. 20 RGE. 14W (E) or (W)

COUNTY Barton

Date Well Completed \_\_\_\_\_

Plugging Commenced 3-28-02

Plugging Completed 3-29-02

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

APR 24 2002

KCC WICHITA

LEASE OPERATOR L.D. Drilling, Inc.

ADDRESS R.R.1 Box 183B Great Bend, Kansas 67530

PHONE#(620) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well OWWD Oil/Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Is plugging proposal was approved on \_\_\_\_\_ (date)

Hay Pfeifer (KCC District Agent's Name).

ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3585'

Show depth and thickness of all water, oil and gas formations.

WELL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	783'	None
				4-1/2"	3585'	2610'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each side. Plugged off bottom with sand to 3400' and 4 sacks cement. Shot pipe @2800' and 2610', pulled up to 1550', pumped 80 sacks cement and 300# hulls, pulled up to 800', pumped 40 sacks cement, and 100# hulls, pulled up to 400', pumped 100 sacks cement and circulated to surface. 60/40pos. Plugging Complete. 10% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L.D. Drilling, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed: that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 19th day of April, 2002

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_

