


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County, Sec. 1 Twp. 20 Rge. 14 R/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{4}$ " or footage from lines
SE SE SW

Lease Owner Raymond Oil Co., Inc.
Lease Name MERTEN Well No. 1
Office Address One Main Place, Suite 900, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above Section Plot

Date Well completed July 26, 19 80
Application for plugging filed July 25 19 80
Application for plugging approved July 25 19 80
Plugging commenced July 26 19 80
Plugging completed July 26 19 80
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well ~~XXXXXXXXXXXX~~ GILBERT TOMAN
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3550
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug Set at 775' with 25 sacks cement thru drill pipe
Middle plug set @ 300' w/25 sacks cement thru drill pipe.
Top plug set at 40' with $\frac{1}{2}$ sack hulls and 10 sacks cement ~~XXXXX~~
5 sacks cement in rat hole.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Duke Drilling Co., Inc.

RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1980
Wichita, Kansas
CONSERVATION DIVISION

STATE OF Kansas COUNTY OF Barton
Leonard Williamson (employee of owner) ~~Raymond Oil Co. operator~~
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson
Box 823 - Great Bend, Ks. 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 28 day of July, 19 80

Dorothy M. Sague
Notary Public.

My commission expires April 11, 1982

DRILLERS' WELL LOG

DATE COMMENCED: July 19, 1980
DATE COMPLETED: July 26, 1980

Raymond Oil Co., Inc.
MERTEN #1
SE 32 SW
Sec. 1-T-20S-RLW
Barton County, Ks.

0 - 177'	Sand
177 - 304'	Shale & Sand Streaks
304 - 722'	Red Bed Shale
722 - 815'	Anhydrite
815 - 2883'	Shale, Salt, Lime
2883 - 2901'	Shale
2901 - 3109'	Lime
3109 - 3133'	Shale
3133 - 3142'	Lime
3142 - 3208'	Shale
3208 - 3219'	Lime & Shale
3219 - 3426'	Lime
3426 - 3500'	Lime, Shale, Congl.
3500 - 3550'	Dolomite
3550'	RTD

ELEVATION: 1675 K.B.

FORMATION DATA

Anhydrite	722'
Savery	2883'
Topeka	2901'
Naehmor	3109'
Toronto	3133'
Douglas	3142'
Brown Lime	3208'
Kansas City	3219'
Base K.C.	3426'
Conglomerate	3445'
Arbuckle	3500'
RTD	3550'

Surface Pipe: Set new 8-5/8" pipe, 20#, at 783' w/400 sacks 50/50 pozmix, 2% gal, 3% c.c.

AFFIDAVIT

STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 28th day of July 1980.

My Comm. Expires:

1-11-1982

Dorothy M. Hoague
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1980
CONSERVATION DIVISION
Wichita, Kansas