

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.009.22307.0000

LEASE NAME Koelsch #1

WELL NUMBER _____

SPOT LOCATION SW NE NE

SEC. 6 TWP. 20 SRGE. 14 W (E) or (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 1/13/84

Plugging Completed 1/24/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P.O. Box 947, Pratt, Ks. 67124

PHONE # () _____ OPERATORS LICENSE NO. _____

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 3691'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	854'	none
				4 1/2"	3690'	1117'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Had bridge at 1171'. Dumped 4 sacks cement on bridge. Shot pipe at 1117'.

Pulled 28 joints of pipe. Put 8 5/8 plug container on. Plugged well with 4 hulls, 12 gel, 25 cement, 3 gel, 1 hull, released plug, & 140 sacks 50/50 poz 4% gel 3% c.c. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

RECEIVED

STATE CORPORATION COMMISSION

JAN 25 1984

SUBSCRIBED AND SWORN TO before me this 24 day of January, 1984

CONSERVATION DIVISION
Wichita, Kansas
My Commission expires:



Irene Hoover
Notary Public