


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barton County. Sec. 14 Twp. 20 Rge. 14 E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
100' S of NE NW SE  
Lease Owner Brougner, Oil, Inc.  
Lease Name Whorton - Cook #1 Well No.  
Office Address Great Bend, Kansas 67530  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plat

Date Well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 11/5/79 19  
Plugging completed 11/7/79 19  
Reason for abandonment of well or producing formation  
~~depleted~~ depleted  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Rankin  
Producing formation Depth to top Bottom Total Depth of Well 3540'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	792	none
				4 1/2"	3539	2909'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Sanded to 3475' and ran 5 sacks cement. Shot pipe at 2921', pulled 73 joints. Halliburton  
pumped 4 sacks hulls, 25 sacks gel, 25 sacks cement, 5 sacks gel, 1 sack hulls, plug and  
100 sacks cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK STATE CORPORATION COMMISSION

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

RECEIVED  
NOV 16 1979

STATE OF KANSAS COUNTY OF RICE CONSERVATION DIVISION  
R. DARRELL KELSO (employee of owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) *R. Darrell Kelso*  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of November, 1979

My commission expires



*Margaret Melcher*  
Notary Public.

15.009.21674.0000

WOODMAN  
PHONE 733-0418  
PHONE 265-7650  
WICHITA, KANSAS

D. J. IANNITTI  
PHONE 792-2921  
GREAT BEND, KANSAS

# WOODMAN & IANNITTI DRILLING COMPANY

*Rotary Drilling Contractors*

1008 DOUGLAS BUILDING  
104 S. BROADWAY  
WICHITA, KANSAS 67202

August 27, 1979

Company;	Brougner Oil, Inc.
Farm;	#1 Whorton-Cook
Location;	100' S of NE NW Se
Section;	14-20-14W
County;	Barton
Contractor;	Woodman & Iannitti Drilling Co.
Comm;	August 19, 1979
Compl;	August 24, 1979
Total Depth;	3540'
Casing;	8 5/8 @ 792 w/450 sx. 4 1/2 @ 3539 w/125 sx.

Figures Indicate Bottom Of Formations;

93	Surface soil & sand
100	Hard sand
160	Sand
580	Shale & sand
786	Sahle & sand
793	Anhy
1310	Shale
1753	Shale & lime
2324	Shale & lime
3025	Lime & shale
3521	Lime & shale
3540	Lime & shale

I certify the above to be a true and correct copy of the driller's log to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.  
*K. T. Woodman*  
K. T. Woodman

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 05 1979  
CONSERVATION DIVISION  
Wichita, Kansas