

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Barton County. Sec. 14 Twp. 20S Rge. 14W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE SE

Lease Owner ALPINE OIL & ROYALTY CO., INC.

Lease Name MOSES Well No. 1

Office Address 800 Bitting Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil well

Date well completed September 12 1958

Application for plugging filed September 14, 1959

Application for plugging approved September 14, 1959


Plugging commenced September 15, 1959

Plugging completed September 22, 1959

Reason for abandonment of well or producing formation non-productive in commercial quantities

If a producing well is abandoned, date of last production September 10 1959

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation Arbuckle Depth to top 3533 Bottom _____ Total Depth of Well 3554 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	240'	Cemented
				5 1/2"	3540	2658.70

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3530 feet and dumped 5 sacks of cement.
Pumped 20 sacks of Jel Mud and 100 sacks of cement into 8 5/8" casing.

RECEIVED
STATE CORPORATION COMMISSION

OCT 6 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Company
Address Box 569 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Dwight J. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
800 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of October, 19 59

My commission expires August 10, 1961

[Signature]
Notary Public.



WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: October 20, 1958

CONTRACTOR: Quaker Drilling Co., Inc.

Completed: October 30, 1958

Moses No. 1-A
NE NE SE Sec. 14-20S-14W
Barton County, Kansas

Elevation: 1882 KB

Casing Record:

Set 8 5/8" casing at 250 feet with 250 sacks pozmix
Set 5 1/2" casing at 3540 feet with 100 sacks pozmixRECEIVED
STATE CORPORATION COMMISSION

OCT 6 1959

CONSERVATION DIVISION
Wichita, Kansas

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Sand	130	Anhydrite	785
Shale and Shells	509	Heebner	3152 -1270
Sand and Red Bed	785	Brown Lime	3252 -1370
Anhydrite	860	Lansing	3262 -1380
Shale and Shells	1600	Conglomerate	3504 -1622
Lime	1710	Arbuckle	3533 -1651
Lime and Shale	2230	Rotary Total Depth	3554 -1672
Lime	2323		
Shale and Lime	3315		
Lime	3504		
Shale and Chert	3533		
Dolomite	3554		

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the NE NE SE of Section 14, Township 20 South, Range 14 West Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: Thomas M. McCaul
Thomas M. McCaul, President

SUBSCRIBED AND SWORN TO before me a Notary Public this 13th day of November, 1958.

Virginia Mundell
Virginia Mundell, Notary Public

MY COMMISSION EXPIRES:
August 10, 1961