

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-009-23,979.0000

LEASE NAME Schmidt

WELL NUMBER B-1

3630 Ft. from S Section Line

3950 Ft. from E Section Line

SEC. 17 TWP. 20 RGE. 14 (E) or (W)

COUNTY Barton

Date Well Completed 7-2-85

Plugging Commenced 7-2-85

Plugging Completed 7-2-85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR WestTech Energy Company, Inc.

ADDRESS RFD #4, Box 101, Great Bend, Kansas 67530

PHONE# (316) 792-5653 OPERATORS LICENSE NO. 5591

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #6

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 3670'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 12 1985
 CONSERVATION DIVISION
 Wichita, Kansas

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surf.	853	8-5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
20 sx. @ 3640', 40 sx. @ 900', 60 sx. @ 250', 10 sx. @ 40', 10 sx. in rathole,
10 sx. in mousehole.
150 sx. 60/40 Pozmix, 4% Gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Woodman-Iannitti Drlg. Co. License No. 5122

Address P.O. Box 308, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

WestTech Energy Company, Inc. (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Catherine E. Peck

(Address) Box 949, Great Bend, KS 67530



AND SWORN TO before me this 11th day of July, 1985

Dianne M. Willesden Dianne M. Willesden

Notary Public

My Commission Expires: 6-28-89

WOODMAN-IANNITTI DRILLING CO.

Date July 2, 1985

Company WesTech Energy Company

Lease Schmidt B

Well No. 1

Legal Description C N/2 S/2 NW, Sec. 17-20S-14W, Barton County, Kansas

Well Depth 3670'

SURFACE INFORMATION

Depth Set 853' Size and Weight of Casing 8-5/8" x 20# & 24#

Number of Sacks 450 Type of Cement 60/40 Pozmix

Additives in Cement 3% CC, 2% Gel

Cementing Company Sun (did circulate, plug down @ 10:30 AM, 6-27-85)

IF CASING IS RUN

Depth Set _____ Size and Weight of Casing _____

Number of Sacks _____ Type of Cement _____

Additives in Cement _____

Cementing Company _____

IF WELL IS PLUGGED

Depth of Each Plug and Number of Sacks on Each 20 sx. @ 3640', 40 sx. @ 900', 60 sx. @ 250', 10 sx. @ 40', 10 sx. in rathole, 10 sx. in mousehole

Type of Cement 60/40 Pozmix

Cement Additives 4% Gel

Cementing Company B.J. Titan (hole plugged @ 6:15 AM)

RECEIVED
STATE CORPORATION COMMISSION

12 1985

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita, Kansas

JUL 12 1985

CONSERVATION DIVISION
Wichita, Kansas