

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.009.01272.0001

LEASE NAME Schmidt (OWW0)

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

3300 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 17 TWP. 20 RGE. 14 (E) or (W)

COUNTY Barton

Date Well Completed 8-3-51

Plugging Commenced 11-4-87

Plugging Completed 11-18-87

LEASE OPERATOR Westech Energy Company, Inc.

ADDRESS Box 949, Great Bend, Kansas 67530

PHONE# (316-792-5653) OPERATORS LICENSE NO. 5591

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Six (6)

Is ACO-1 filed? If not, is well log attached? With application

Producing Formation Depth to Top Bottom T.D. 3,689'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	854'	None
				5-1/2"	3687'	2,610.81'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3250' and 5 sacks cement. Shot casing at 2800' and 2600'. Pulled 66 joints of 5-1/2" casing. Allied squeezed well with 5 sacks hulls and 100 sacks A.T.L. cement. Maximum press was 600 psi and shutin 400 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.


James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 18th day of November, 19 87

My Commission Expires:



STATE CORPORATION COMMISSION
Notary Public
Iona M. Leatherman
NOV 18 1987