

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-009-23,381-0000

LEASE NAME Schmidt

WELL NUMBER 2

SPOT LOCATION 1320' FEL 1650'
FSL NW/4

SEC. 17TWP. 20S RGE. 14(E)OR(W)

COUNTY Barton

DATE WELL COMPLETED 12-14-83

PLUGGING COMMENCED 12-14-83

PLUGGING COMPLETED 12-14-83

TYPE OR PRINT

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Wes-Tech Energy, Inc.

ADDRESS R.R. #4, Box 101, Great Bend, Kansas 67530

PHONE # (316) 792-5653 OPERATORS LICENSE NO. 5591

CHARACTER OF WELL D&A
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Stafford, Kansas

Is ACO-1 FILED? Yes IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM _____ T.D. 3650'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

20 sx. @ 3590', 90 sx @ 850', 10 sx. @ 40', 10 sx. in Rathole, 10 sx. in Mousehole

Total 140 sx. 50/50 Poz-mix, 6% Gel

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Sun Oilwell Cementing LICENSE No. _____

ADDRESS P.O. Box 169, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, SS.

K.T. Woodman (EMPLOYEE OF OPERATOR) OR
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND
CORRECT, SO HELP ME GOD.

(SIGNATURE) K.T. Woodman


(ADDRESS) 1022 Union Center, Wichita, KS

SUBSCRIBED AND SWORN TO BEFORE ME THIS 16th DAY OF December, 1983

Kathryn A. Voigt
NOTARY PUBLIC

Kathryn A. Voigt

MY COMMISSION EXPIRES: April 20, 1985



RECEIVED
STATE CORPORATION COMMISSION

FORM CP-4
REVISED 06-83

DEC 1 9 10AM '83

CONSERVATION DIVISION
Wichita, Kansas

12-19-1983

K. T. WOODMAN
 RES. PHONE 733-0418
 OFF. PHONE 265-7650
 WICHITA, KANSAS

D. J. IANNITTI
 PHONE 792-2921
 GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY
Rotary Drilling Contractors

1022 UNION CENTER
 150 N. MAIN
 WICHITA, KANSAS 67202

December 16, 1983

Company:	Wes-Tech Energy, Inc.
Farm:	Schmidt #2
Location:	1320' FEL 1650' FSL NW/4,
Section:	17-20S-14W
County:	Barton
Contractor:	Woodman & Iannitti Drilling Company
Total Depth:	3650'
Comm:	December 7, 1983
Comp:	December 14, 1983
Casing:	8-5/8" 24# & 20# set @ 857' w/450 sx. 60/40 Poz-mix, 2% Gel, 3% CC

Figures Indicate Bottom Formations:

70	Sand
291	Clay & Shale
373	Dakota Sand
635	Shale & Shells & Red Bed
845	Red Bed
857	Anhydrite
869	Anhydrite
1400	Shale
1938	Shale
2300	Shale
2640	Shale & Lime
2930	Lime & Shale
3080	Lime
3250	Lime & Shale
3401	Shale & Lime
3478	Lime
3527	Lime & Shale
3588	Lime
3650	Arbuckle

I certify the above to be a true and correct copy of the Drillers Log to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING COMPANY

K. T. Woodman
 K.T. Woodman, Partner