


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver, Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

BARTON

County. Sec. 30 Twp. 20 Rge. 14 (X) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW

Lease Owner GEORGE A. REED

Lease Name UNRUH #1 Well No.

Office Address 1301 UNION NATL. BLDG., WICHITA, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed 11/26/66 19

Application for plugging filed 11/26/66 19

Application for plugging approved 11/26/66 19

Plugging commenced 11/26/66 19

Plugging completed 11/26/66 19

Reason for abandonment of well or producing formation TOO LOW STRUCTURALLY

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well DONALD TRUAN, RUSSELL, KANSAS

Producing formation Depth to top Bottom Total Depth of Well 3636 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	868.32	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED WITH HEAVY MUD to 350'. SET PLUG. PUT IN 1/2 SACK HULLS AND 25 SACKS CEMENT. FILLED WITH HEAVY MUD TO 40'. SET PLUG. PUT IN 1/2 SACK HULLS AND 10 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1967

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor C-G DRILLING CO. (If additional description is necessary, use BACK of this sheet)

Address 107 RULE BUILDING, WICHITA, KANSAS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. G F GALLOWAY

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) G F GALLOWAY

107 RULE BUILDING, (Address)

Subscribed and Sworn to before me this 28th day of NOVEMBER, 1966

My commission expires JAN. 23, 1968

Phyllis McJimsey
PHYLLIS MCJIMSEY Notary Public.



W E L L L O G

OPERATOR: GEORGE A. REED
 WELL NAME: UNRUH #1 LOCATION: SW SW NW Sec 30-20-14W
 COUNTY: BARTON STATE: KANSAS
 WELL COMMENCED: 11/17/66 WELL COMPLETED: 11/26/66
 ELEVATION: 1913 KB TOTAL DEPTH: 3636'
 PRODUCTION: DRY & ABANDONED RIG NO: 2
 CASING - 8-5/8": 26 its. 868, 32' W/225 sx Pozmix 200 sx Common Cmt.
 5-1/2": _____

All Measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	480	SAND	1/4° 400'	
480	850	RED BED	1/4° 1350'	
850	860	RED SHALE	3/4° 1830'	
860	895	ANHYDRITE	1° 2330'	
895	1575	SHALE & SHELLS	1 1/8° 2850'	
1575	3060	LIME & SHALE	1° 3325'	DST #1 3625-3630'
3060	3636	LIME		DST #2 3630-3636'
3636		ARBUCKLE		

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 4 1967
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS) SS:
 COUNTY OF SEDGWICK)
 The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.
 By G. F. Galloway
 G. F. GALLOWAY

SUBSCRIBED AND SWORN TO, BEFORE ME, This 29th day of NOVEMBER, 1966.

My comm. exp: ~~XXX/20/XX/67X~~
 Jan. 23, 1968

Phyllis McJimsey
~~XXXXXX~~ - Notary Public
 PHYLLIS McJIMSEY

