

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15,009, 23,697.0000

LEASE NAME Weathers

WELL NUMBER #1-30

1485 Ft. from S Section Line

330 Ft. from E Section Line

SEC 30 TWP. 20 RGE 14 (E) or (W)

COUNTY Barton

Date Well Completed \_\_\_\_\_

Plugging Commenced 12-2-87

Plugging Completed 12-16-87

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR WesTech Energy Co., Inc.

ADDRESS Box 949, Great Bend, Ks. 67530

PHONE# (316-792-5653) OPERATORS LICENSE NO. 5591

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Four (4)

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 3680'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	870'	None
				5-1/2"	3675'	2,851.05'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3575' and 5 sacks cement. Shot casing at 2800'. Pulled 66 jts. of 5-1/2" casing. BJ Titan squeezed well with 3 sacks hulls and 125 sacks Thrifty-Mix cement blended with 2 sacks hulls. Maximum pressure was 650 kpsi and shutin was 600 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold  
Box 698, Gr. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 17th day of December, 1987

Jon M. Leatherman  
 Notary Public

My Commission Expires:

