

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

#1

API NUMBER 15-009-23,947.0000

LEASE NAME Ohnmacht

WELL NUMBER #3

3290 Ft. from S Section Line

4630 Ft. from E Section Line

SEC. 29 TWP. 20 RGE. 14 (E) or (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 11-19-88

Plugging Completed 11-30-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Westech Energy Co., Inc.

ADDRESS Box 949, Great Bend, Kansas 67530

PHONE# (316) 792-5653 OPERATORS LICENSE NO. 5591

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 28, 1988 (date)

by Gilbert Scheck (KCC District Agent's Name).

Is ACO-1 filled? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom T.D. 3680'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	866'	None
				5-1/2"	3679'	2,714.42'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3550' and 5 sacks cement. Shot casing at 2850' and 2650'. Pulled 63 joints of 5-1/2" casing. Allied plugged well with 500# hulls and 200 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 500 psi and shutin 300 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Westech Energy Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Great Bend, Kansas 67530

SCRIBED AND SWORN TO before me this 5th day of December, 1988

Lona M. Leatherman
Notary Public

My Commission Expires _____

NOTARY PUBLIC
KANSAS
LONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-91

RECEIVED
STATE CORPORATION COMMISSION
DEC 6 1988
CONSERVATION DIVISION
Wichita, Kansas

12-6-1988