

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-23,811-0000

LEASE NAME Ohnmacht

WELL NUMBER #2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2640 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 29 TWP. 20 RGE. 14 (E) or (W)

COUNTY Barton

LEASE OPERATOR WestTech Energy, Co

ADDRESS Box 949, Great Bend, Kansas 67530

PHONE 816-792-5653 OPERATORS LICENSE NO. 5591

Date Well Completed _____

Character of Well Oil

Plugging Commenced 12-27-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-28-91

The plugging proposal was approved on December 28, 1990 (date)

by Gilbert Scheck (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3680'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	870'	None
				5-1/2"	3669'	2,419.67'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3550' and 5 sacks cement. Shot casing at 2800', 2718', 2635', 2523', 2400'. Pulled 59 joints of 5-1/2" casing. Allied plugged well with 25 sacks cement 500# hulls and 175 sacks 60/40 pozmix cement with 8% gel. Maximum pressure was 300 psi and shutin 50 psi.

Name of Plugging Contractor Rockhold Engineering, Inc.

JAN 30 1991
License No. 5111

Address Box 698, Great Bend, Kansas 67530

CONSERVATION DIVISION
Wichita, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: WestTech Energy Co.

1-30-1991

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

James W. Rockhold
(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 29th day of January, 1991

Jona M. Leatherman

Notary Public

My Commission Expires _____

