


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barton County, Sec. 15 Twp 20S Rge. 13W (E) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner Alpine Oil & Royalty Co., Inc.
Lease Name Voight Well No. 1
Office Address 800 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed January 3, 1958 19
Application for plugging filed October 31, 1958 19
Application for plugging approved October 31, 1958 19
Plugging commenced November 1, 1958 19
Plugging completed November 6, 1958 19
Reason for abandonment of well or producing formation non-productive in commercial quantities
If a producing well is abandoned, date of last production October 11, 1958 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation Arbuckle Depth to top 3484 Bottom _____ Total Depth of Well 3525 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 168' | Cemented |
| | | | | 5 1/2" | 3487' | 2724.39 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3475' - dumped 5 sacks cement - pumped in 25 sacks Jell Mud and 80 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
DEC 1 - 1958
CONSERVATION DIVISION
Wichita, Kansas
12-1-1958

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D Casing Pulling Company - License #236
Address Box 569 - Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Thomas M. McCaul
800 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of November, 1958.
My commission expires August 10, 1961
Regina Marshall Notary Public.

PLUGGING
FILE SEC 15 T 20 R 13W
BOOK PAGE 141 LINE 31

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: November 29, 1957

Contractor: Quaker Drilling Co., Inc.

Completed: December 8, 1957

Voight No. 1
SE SE SE S⁴c. 15-20S-13W
Barton County, Kansas

Elevation: 1871 KB

Casing Record

Set 8 5/8" casing at 168 feet with 200 sacks pozmix
Set 5 1/2" casing at 3487 feet with 125 sacks pozmix

(Figures Indicate the Bottom of the Formations)

| <u>FORMATION</u> | <u>DEPTH</u> | <u>FORMATION TOPS</u> | |
|-----------------------|--------------|-----------------------|------------|
| Surface Clay and Sand | 69 | Anhydrite | 705 |
| Hard Brown Sand | 72 | Heebner | 3090 -1219 |
| Sand | 96 | Brown Lime | 3214 -1343 |
| Hard Brown Sand | 98 | Lansing | 3227 -1358 |
| Sand and Shale | 116 | Arbucle | 3484 -1613 |
| Hard Brown Sand | 122 | Rotary Total Depth | 3493 -1622 |
| Shale and Shells | 168 | | |
| Hard Sand | 173 | | |
| Shale and Shells | 590 | | |
| Red Bed | 705 | | |
| Anhydrite | 735 | | |
| Shale and Shells | 1675 | | |
| Sandy Lime and Shale | 1850 | | |
| Shale and Lime | 2025 | | |
| Sandy Lime and Shale | 2185 | | |
| Shale and Shells | 2645 | | |
| Lime and Shale | 3370 | | |
| Lime | 3435 | | |
| Lime and Shale | 3484 | | |
| Dolomite and Shale | 3493 | | |

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the SE SE SE SEC. 15, Township 20 South, Range 13 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By:

Thomas M. McCaul
Thomas M. McCaul, President

SUBSCRIBED AND SWORN to before me a Notary Public this 10th day of December, 1957.

Virginia Mandell
Virginia Mandell, Notary Public

MY COMMISSION EXPIRES:
August 10, 1961

RECEIVED
STATE CORPORATION COMMISSION

DEC 1 - 1958
CONSERVATION DIVISION

PLUGGING
FILE SEC 15 T 20 R 13W
BOOK PAGE 141 LINE 31