

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Barton SEC. 24 TWP. 20S RGE. 14 E/W  
Location as in quarters or footage from lines:  
SE NW SW

		24	
x			

Locate Well  
correctly on above  
Section Platt.

Lease Owner Sabre Exploration, Inc. & Carnes-Dunne, Inc.  
Lease Name Maybach Well No. #1  
Office Address 510 120 Bldg., Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): dry hole  
Date Well Completed 10/21/82  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 10/21/82 3:00 PM  
Plugging completed 10/21/82 8:30 PM  
Reason for abandonment of well or producing formation dry

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Unknown  
Producing formation none Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3560'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

180 sx. total 50/50 pozmix (4% gel, 3% c.c.)  
Ran 20 sx. @ 3510'  
100 sx. @ 810'  
40 sx. @ 270'  
10 sx. @ 40' w/ bridge  
10 sx. in rathole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.


Matthew W. Totten (~~EMPLOYEE OF OWNER~~) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Matthew W. Totten  
510 120 Bldg., Wichita, KS  
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of November, 19 82

Dorlee J. Kremer  
Dorlee J. Kremer Notary Public.

Commission expires: 3/29/86



15.009.22925.0000



P.O. Box 18595 / Wichita, KS 67218

Wichita (316) 685-1402

Rig # 1 (316) 672-5663  
Unit 2905

Rig # 2 (316) 793-7859  
Unit 7040

DRILLERS WELL LOG

RECEIVED  
STATE CORPORATION COMMISSION

NOV 30 1982

CONSERVATION DIVISION  
Wichita, Kansas

RE: Maybach #1  
SE, NW, SW, 24-20S-R14W  
Barton County, Kansas

Commenced: 10/9/82  
Completed: 10/21/82  
Operator: Sabre Exploration, Inc.


\*\*\*\*\*

<u>DEPTH</u>	<u>FORMATION</u>	<u>REMARKS</u>
0-791	Surface sand	Ran 19 jts new 8 5/8" csg 799',
791-2803	Anhydrite	Set at 809'. Cemented w/400 sks
2803-3150	Topeka	common, 3% gel 2% cc, 60/40 Posmix
3150-3161	Heebner	Job complete at 5:00 AM 10/11/82.
3161-3182	Toronto	
3182-3255	Douglas Shale	
3255-3265	Brown Lime	
3265-3444	Lansing	D&A: First plug 3510' 20 sks.
3444-3493	Stark Shale	Second plug 810' 100 sks.
3493-3526	B/Kansas City	Third plug 270' 40 sks. Solid
3526-3560	Arbuckle	bridge plug 40' sks. 10 sks in
3560-RTD		rat hole. Cemented w/180 sks
		50/50 Posmix 4% gel 3% cc.
		Job complete 8:30 PM 10/21/82.

\*\*\*\*\*

STATE OF KANSAS, County of Sedgwick:ss

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.



*Dorothy T. Smith*  
Dorothy T. Smith, Notary Public

LANDMARK ENERGY CORPORATION

*D.W. Smith*  
D. W. Smith, Sec., Treas.