

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barton County, Sec. 24 Twp. 20s Rge. 14 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines SE/4 SW/4 SW/4

Lease Owner Carl Boxberger

Lease Name Maybeck Well No. 1

Office Address P.O. Box 474, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 9 19 62

Application for plugging filed March 9 19 62

Application for plugging approved March 9 19 62


Plugging commenced March 9 19 62

Plugging completed March 9 19 62

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Don Truan

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3597 Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 400'
Set wooden plug @ 400' and 20 sacks cement thru drill pipe.
Set wooden plug @ 250' and 20 sacks cement thru drill pipe.
Filled hole with heavy mud to 35'
1/2 sack hulls and 10 sacks cement
Plugged rat hole



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.

Address P.O. Box 823, Great Bend, Ks.

STATE OF KANSAS, COUNTY OF BARTON, ss.

Carl Boxberger (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl Boxberger

P.O. Box 474, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this _____ day of March, 19 62

My commission expires 6-24-63

Clair E. Stimson
Clair E. Stimson Notary Public.



DRILLER'S WELL LOG

Date Commenced: March 1, 1962
Date Completed: March 9, 1962

Carl Boxberger
MAYBACK # 1
SE/4 SW/4 SW/4
Section 24-R20s-T14w
Barton County, Kansas

0	-	150°	Sand
150	-	259°	Shale & Shells
259	-	795°	Red Bed
795	-	825°	ANHYDRITE
825	-	1650°	Shale-S,ells-Salt
1650	-	2185°	Shale & Lime Stringers
2185	-	2615°	Shale & Lime
2615	-	2830°	Lime & Shale
2830	-	3161°	Lime
3161	-	3173°	Shale & Lime HEEBNER
3173	-	3191°	Lime TORONTO
3191	-	3268°	Shale DOUGLAS
3268	-	3278°	Lime Shale BROWN LIME
3278	-	3506°	Lime LANSING
3506	-	3597°	CONGLOMERATE
3597	-		R.T.D.

ELEVATION: 1903 K.F.

FORMATION DATA:

ANHYDRITE	795
HEEBNER	3161
TORONTO	3173
DOUGLAS	3191
BROWN LIME	3268
LANSING	3278
CONGLOMERATE	3506
R.T.D.	3597

SURFACE PIPE: Set 259°
of 8-5/8" casing with
190 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 13 1962

CONSERVATION DIVISION
Wichita, Kansas

AFFIDAVIT

STATE OF KANSAS
COUNTY OF BARTON) ss.

Lewis O. Chubb, of lawful age, does swear that the facts
and statements herein contained are true and correct to the best of
his knowledge.


Lewis O. Chubb

Subscribed and sworn to before me this 12th day of March, 1962.


Clair E. Stinson-NOTARY PUBLIC

My Comm. Expires: 6-24-63