

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barton County, Sec. 24 Twp. 20S Rge. XE) 14 (W)

Location as "NE/CNW/SW" or footage from lines C N/2 NW/4 NW/4

Lease Owner Sterling Drilling Company

Lease Name Maybach Well No. 1

Office Address Sterling, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 15 19 59

Application for plugging filed February 15 19 59

Application for plugging approved February 15 19 59


Plugging commenced February 15 19 59

Plugging completed February 15 19 59

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3593 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	240'	8-5/8"	240'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Circulated with heavy mud. Pushed 1/4th sack hulls and Halliburton plug to 230'. Mixed 25 sacks cement, poured through 7 joints of open end of drill pipe. Filled hole to within 40' K. B. Built solid bridge of hulls and Halliburton plug, used 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 19 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sterling Drilling Company
Address Sterling, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner
F. A. Wuellner
Sterling, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of February, 19 59

My commission expires Jan. 22, 1962
Bernard Landermilch Notary Public.

PLUGGING
FILE JEC 24 T 20 R 14W
BOOK PAGE 19 LINE 26

STERLING DRILLING COMPANY
Sterling, Kansas

WELL LOG ----- MAYBACH #1
Located: C N/2 NW/4 NW/4, Section 24-20S-14W, Barton County, Kansas

OWNER: Sterling Drilling Company, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: 2-6-59
COMPLETED: 2-15-59

ROTARY TOTAL DEPTH: 3593'

LOG

0 -	175	Sand & Clay
175 -	260	Shale
260 -	730	Sand, Red Bed & Shale
730 -	1410	Shale
1410 -	1680	Shale & Lime
1680 -	1800	Lime
1800 -	1950	Lime & Shale
1950 -	2070	Lime
2070 -	2895	Lime & Shale
2895 -	3140	Lime
3140 -	3255	Lime & Shale
3255 -	3530	Lime
3530 -	3593	Conglomerate R.T.D.

CASING RECORD

Set 8-5/8" surface casing @ 240'
with 250 sacks bulk pozmix, 2% c.c.

PRODUCTION RECORD

Plugged & Abandoned

RECEIVED
STATE CORPORATION COMMISSION
FEB 19 1959
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING	
FILE SEC.	24 T 20 R14W
BOOK PAGE	19 LINE 26