

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Barton County, Sec. 23 Twp. 20S Rge. 14W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SW SW

Lease Owner B. H. Hilburn

Lease Name Janne Well No. 2

Office Address 1514 Mercantile Sec. Bldg, Dallas, Texas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8/6/1961

Application for plugging filed 8/6/1961

Application for plugging approved 8/6/1961

Plugging commenced 8/6/1961

Plugging completed 8/6/1961

Reason for abandonment of well or producing formation No commercial

quantities of oil or gas encountered

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, Stockton, Kansas

Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 3596 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface				8-5/8	333'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Drilling mud was introduced into the hole to a top level of 240 feet. A cement plug was set at 240' with 20 sacks of cement. Mud was again introduced into the hole and a surface plug set at 35' with 10 sacks of cement. The casing was then cut off below ground level and the location abandoned.

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Tomlinson-Kathol, Inc.
Address 414 Union Center, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Gerald J. Kathol

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gerald J. Kathol
414 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of August, 1961

My commission expires 1/19/65

Esther Lamore
Notary Public.

DRILLERS LOG
 B. H. HILBURN
 NE SW SW, SEC. 23-20S-14W
 BARTON COUNTY, KANSAS
 # 2 JANNE

Contractor - Tomlinson-Kathol, Inc.

Commenced: 7/27/61
 Completed: 8/6/61
 Elevation: 1895 KB

From	To	Description	Remarks
0	100	Sand	
100	280	Clay 0 Sand	
280	325	Sand	
325	818	Shale	332' 8-5/8" Surf. Csg. w/225 sacks
818	834	Anhydrite	
834	1780	Shale	
1780	1883	Lime - Shale	
1883	1965	Shale	
1965	2092	Lime, shale	
2092	2227	Shale & Lime	
2227	2321	Lime - Shale	
2321	2505	Shale - Lime	
2505	2926	Shale	
2926	2985	Lime & Shale	
2985	3060	Lime	
3060	3106	Lime & Shale	
3106	3195	Shale & Lime	
3195	3353	Lime	
3353	3383	Lime & Shale	
3383	3448	Lime	Heebner 3163
3448	3533	Lime & Shale	Toronto 3177
3533	3556	Conglomerate	Brown Lime 3265
3556	3596	Arbuckle	Lansing 3277
3596		Rotary Total Depth	K.C. 3508
			Conglomerate 3522
			Arbuckle 3556


RECEIVED
 STATE CORPORATION COMMISSION
 AUG 10 1961
 CONSERVATION DIVISION
 Wichita, Kansas

I certify to the best of my knowledge and belief, the above represents a true and accurate Driller's Log record of the captioned well.


 Richard C. Davis, Geologist

State of Kansas)
 County of Sedgwick)

Subscribed and sworn to before me this 8th day of August, 1961.


 Esther Lamone, Notary Public

My Commission Expires: 1/19/65