

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

BARTON County. Sec. 23 Twp. 20 Rge. 14 W (W)

Location as "NE/CNWSW" or footage from lines SW NW SW

Lease Owner PETROLEUM, INC.

Lease Name JANNE Well No. 1

Office Address ROUTE 2, GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) OIL

Date well completed NOVEMBER 15 19 52

Application for plugging filed MARCH 27 19 59

Application for plugging approved MARCH 30 19 59

Plugging commenced APRIL 2 19 59

Plugging completed APRIL 9 19 59

Reason for abandonment of well or producing formation DEPLETION OF PRODUCIBLE ZONES

If a producing well is abandoned, date of last production MARCH 18 19 59

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well DONALD TRUAN, GORHAM, KANSAS

Producing formation KANSAS CITY Depth to top 3279' Bottom 3516' Total Depth of Well 3558' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
KANSAS CITY	LITTLE OIL & WATER	3341'	3346'	8-5/8"	486'	NONE
		3323'	3329'	5-1/2"	3544.50'	2900'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

(PLUGGED BACK TO 3374')

FILLED HOLE WITH CRUSHED ROCK FROM 3374'-3310'. PLACED 5 SACKS CEMENT ON TOP OF ROCK. GLOBE OIL WELL CEMENTING COMPANY PUMPED 20 SACKS MUD ON TOP OF CEMENT FOLLOWED BY A PLUG. FILLED HOLE TO BASE OF WELL CELLAR WITH 100 SACKS CEMENT, 4% GEL. CEMENT SETTLED APPROX. 30'. PLACED ADDITIONAL 9 SACKS TO BASE OF WELL CELLAR.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 15 1959  
CONS. DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor MORGAN WELL PLUGGING SERVICE

Address 102 WEST 18TH STREET, HUTCHINSON, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.

DON SEARLE (employee of owner) or (~~agent~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle

ROUTE 2, GREAT BEND, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 14TH day of APRIL 19 59

My commission expires JULY 11, 1960

[Signature]  
Notary Public.

PLUGGING  
FILE SEC. 23 T. 20 R. 14W  
BOOK PAGE 26 LINE 7

DRILLER'S LOG JANNE NO. 1

Petroleum, Inc., Operator	Section 23, Twp. 20S, Rge. 14W
Contractor, Garvey Drilling Company	Location: SW NW SW
Drilling Commenced: October 21, 1952	County: Barton County, Kansas
Drilling Completed: October 31, 1952	R.T.D.: 3547'
Casing Record: 8 5/8" @ 486' w/275 sax	
5 1/2" @ 3455 1/2' w/100 sax	

Figures below indicate bottom of formation

40	Clay and Sand	
160	Sand	
260	Shale	Heebner: 3163 (-1267)
347	Sand	Brown Lime: 3267 (-1471)
818	Red Bed	Lansing: 3279 (-1383)
836	Anhydrite	Arbuckle: 3542 (-1646)
1595	Shale & Shells	
1790	Lime & Shale	DST #1, 3282-3352, open 1 hr., rec. 90' gas cut mud, 60' oil cut mud, 90' very heavily oil cut mud, 360' froggy oil, 760# BHP.
2105	Lime	
3033	Lime & Shale	DST #2, 3394-3447, open 1 hour, rec. 310' muddy salt water, 1170# BHP.
3181	Lime	
3303	Lime & Shale	
3530	Lime	
3542	Conglomerate	
3547	Lime	
3547'	R.T.D.	

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By W W Fisher

STATE OF KANSAS )  
 ) SS:  
 COUNTY OF SEDGWICK )

Subscribed to and sworn to before me, a Notary Public in said county and state, this 4th day of November, 1952.

Charlotte Friedman  
 Notary Public

My commission expires: October 13, 1954.

PLUGGING	
FILE	SEC. 23 T. 20 R. 14W
BOOK	PAGE 26 LINE 7