

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barton SEC. 22 TWP. 20 RGE. 14 R/W
Location as in quarters or footage from lines:
NW SW NE

Locate Well
correctly on above
Section Platt.

Lease Owner Rockwood Petroleum Co.
Lease Name Neff Well No. #1
Office Address 815 Douglas Bldg., Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed June 13, 1981
Application for plugging filed June 13, 1981
Plugging commenced June 13, 1981
Plugging completed June 13, 1981
Reason for abandonment of well or producing formation _____

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation _____ Depth to top _____ bottom _____ T.D. 3600

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plu - set at 830' with 30 sacks 50/50 pozmix, 3% cc, 2% gel thru drill pipe
Middle plug - set at 200' with 30 sacks 50/50 pozmix, 3% cc, 2% gel thru drill pipe
Top Plug - set at 40' with solid - 1/2 sack hulls
10 sacks in rat hole

RECEIVED
STATE CORPORATION COMMISSION

JUN 22 1981

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.
Box 823, Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Darrel Anderson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Darrel Anderson
(Address) _____

SUBSCRIBED AND SWORN TO before me this 19th day of June, 1981

Alvin M. Hogue
Notary Public.

My Commission expires: April 11, 1982

DRILLERS WELL LOG

DATE COMMENCED: June 7, 1981
DATE COMPLETED: June 13, 1981

Rockwood Petroleum Co.
NEFP #1
NW SW NE
Sec. 22-20-14
Barton County, KS

0 - 826' Surface soil, Sand, Shale
826 - 856' Anhydrite
856 - 3176' Shale & Lime
3176 - 3294' Lime & Shale
3294 - 3555' Shale & Lime
3555 - 3600' Dolomite
3600' RTD

ELEVATION: 1896 K.B.

FORMATION DATA

Anhydrite 826'
Rebner 3176'
Lansing 3294'
Arbuckle 3555'
RTD 3600'

Surface Pipe: Set 828' of 8-5/8" pipe, 2% gel, 3% cc. with 425 sacks common 2% gel, 3% c.c.

AFFIDAVIT

STATE OF KANSAS
COUNTY OF BARTON) ss

Darzel Anderson of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Subscribed and sworn to before me this 19 day of June 1981.

My Comm. Expires:

4-11-1982

[Signature]

Notary Public

RECEIVED
STATE CORPORATION COMMISSION
JUN 22 1981
CONSERVATION DIVISION
Wichita, Kansas