


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Barton County, Sec. 22 Twp 20S Rge. 14 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines NE NE SW
Lease Owner Mayfield Petroleum Co.
Lease Name Asher Well No. 1
Office Address 300 Bitting Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-25 19 66
Application for plugging filed 9-25 19 66
Application for plugging approved 9-25 19 66
Plugging commenced 9-25 19 66
Plugging completed 9-25 19 66
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3604' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	835'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with heavy rotary mud to 350 ft. Bridge at 350 ft. with hulls and 25 sacks cement. Hole filled with mud to 40 ft. Bridge at 40 ft. with hulls and 11 sacks cement. Rathole capped with 4 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 29 1966
CONSERVATION DIVISION
WICHITA, KANSAS

9-29-1966

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor White & Ellis Drilling, Inc. License # 209
Address Box 448, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
Ernest Sifford, employee of contractor (employee of owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford
Box 448, El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of September, 19 66

My commission expires September 26, 1968 Notary Public.

Casing Record

15.009.30441.0000

Location: NE NE SE SW
 Section: 22-206-14W
 Barton County, Kansas
 Farm: Asher #1
 Well Owner: Mayfield Petr. Co.
 Contractor: White & Ellis
 Drilling, Inc.
 Commenced: 9-16-66
 Completed: 9-25-66
 Elevation: 1888' - G.L.
 1893' - K.B.

T. D. 3604'

Kelly Bushing Measurement 5' above ground level.

<u>FORMATION</u>	<u>DEPTH</u>
Sand	0-130
Shale	285
Sand	380
Shale & Lime	828
Anhydrite	855
Shale	1185
Shale & Lime stks.	1675
Lime	2110
Shale & Lime stks.	2320
Lime & Shale	2560
Shale & Lime stks.	2685
Lime & Shale stks.	2740
Shale & Lime	2785
Shale	2828
Lime	3199
Shale	3268
Lime	3506
Shale	3544
Conglomerate	3604

TOPS

Anhydrite	826
Heebner	3199
Brown	3268
Kansas City	3279

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 29 1966
 CONSERVATION DIVISION
 Wichita, Kansas

Dry Hole, Plugged
& Abandoned