


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas



Barton County, Sec. 21 Twp. 20 Rge. (E) 14(W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW SW
Lease Owner E. H. Adair
Lease Name Tuggle Well No. 1
Office Address 407 W-H Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 3, 1951
Application for plugging filed December 3, 1951
Application for plugging approved December 3, 1951
Plugging commenced December 4, 1951
Plugging completed December 4, 1951
Reason for abandonment of well or producing formation Barren

If a producing well is abandoned, date of last production 19...
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Great Bend
Producing formation Depth to top Bottom Total Depth of Well 3620 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Copy of well log attached						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to... feet for each plug set.

Placed plug at 270', put 15 sx cement on plug through drill pipe filled hole with mud to 30' of surface, placed wooden plug and filled hole with 18 sx cement, filled to surface.

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to E. H. Adair Oil Company
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
RUSSELL I. BAKER (employee of owner) or ~~operator~~ of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Russell I. Baker
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 29th day of December, 1951
My commission expires September 15, 1953 Notary Public.

PLUGGING
FILE SEC 21 T 20 R 14 W
BOOK PAGE 129 1/2 S

1-2-1952

E. H. ADAIR OIL COMPANY

Sec. 21

T. 20

15.009.01107.0000

R. 14 W

Tuggle No. 1

Barton County - SW SW SW

Total Depth 3620'

Comm. 11/23/51 Comp. 12/3/51

863' s/csg. w/375 sx cement Elevation 1902 DF
1899 Gr

Sand	0-85
Sand & Shale	85-525
Shale	525-790
Shale, red	790-861
Anhydrite	861-890
Shale	890-1748
Shale & Shells	1748-1900
Lime	1900-2040
Shells & Shale	2040-2108
Lime & Shale	2108-2268
Shale & Shells	2268-2516
Shale	2516-2740
Shale & Shells	2740-2910
Lime	2910-2956
Shale & Lime	2956-3070
Lime	3070-3277
Shale	3277-3308
Lime	3308-3594
Shale	3594-3599
Lime	3599-3620 Rotary

Certified Correct

R. H. Baker

PLUGGING
 FILE SEC 21 T 20 R 14 W
 BOX PAGE 129 LINE 5

JAN - 2