

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Pawnee SEC. 5 TWP. 20S RGE. 19W E/W  
Location as in quarters or footage from lines:

NW NW SE


Lease Owner National Cooperative Refinery Association

Lease Name Van Rensselaer #2 Well No. \_\_\_\_\_

Office Address Box 6 Great Bend, Kansas 67530

Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_

Date Well Completed \_\_\_\_\_

Application for plugging filed \_\_\_\_\_

Plugging commenced 2-23-82

Plugging completed 2-26-82

Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	355'	none
				5-1/2"	4298'	2422'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged of bottom with sand to 4150' and ran 5 sacks cement. Shot casing @3220', 3005', 2820', 2605' and 2415'. Pulled atotal of 77 joints of pipe. Plugged well with 4 sacks hulls, 15 sacks gel, 75 sacks cement, 1 sack hulls, 10 sacks gel, released plug and displaced with 75 sacks cement, 50/50 pos, 4% gel, 3% cc. Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

RECEIVED  
3-4-1982  
MAR 4 1982

(Signature) R. Darrell Kelso

Box 176 Chase, Kansas 67524

(Address)

CONSERVATION DIVISION  
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 19 82



Irene Hoover  
Notary Public.

My Commission expires: \_\_\_\_\_

**COPY**

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- THUNDERBIRD DRILG., INC.  
Farm Van Rensselaer No. 2

SEC. 5 T. 20 R. 19W  
NW NW SE


Total Depth. 4300  
Comm. 7-28-64  
Shot or Treated.

Comp. 8-9-64

County Pawnee  
KANSAS

Contractor. Company Tools  
Issued. 12-26-64

**K. G. S. LIBRARY**



CASING:

8 5/8" 355' 200 sx.cem.  
5 1/2" 4298' 100 sx.cem.

Elevation. 2239KB

Production. 156 BOPD, 15% wtr.

Figures Indicate Bottom of Formations.

clay & shale	355
shale & red bed	800
sand & shale	1185
shale	1380
anhydrite	1415
shale & shells	1920
shale & lime	2540
lime & shale	3085
shale & lime	3210
lime & shale	3610
lime	4223
sand & lime	4245
lime	4300 RTD

SCOUT TOPS:

Anhydrite sp.	1380
Heebner	3676
Toronto	3694
Douglas	3704
Lansing	3723
Marmaton	4118
Pawnee Sand	4174
Fort Scott	4192
Base Fort Scott	4202
Cherokee Sand	4216
Mississippi	4286

RECEIVED  
STATE CORPORATION COMMISSION

OCT 15 1964

CONSERVATION DIVISION  
Wichita, Kansas