

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

## WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Pawnee SEC. 5 TWP. 20S RGE. 19W E/W  
Location as in quarters or footage from lines:  
SE NE SW


Locate Well  
correctly on above  
Section Platt.

Lease Owner National Cooperative Refinery Association.  
Lease Name Van Rensselaer #1 Well No.   
Office Address Box 6 Great Bend, Kansas 67530  
Character of Well (Completed as Oil, Gas or Dry Hole):   
Date Well Completed   
Application for plugging filed   
Plugging commenced 2-16-82  
Plugging completed 2-26-82  
Reason for abandonment of well or producing formation

Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation  Depth to top  bottom  T.D. 4290'

Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	352'	none
				5-1/2"	4276'	2317'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from  feet to  feet for each plug set.

Plugged off bottom with sand to 4150' and ran 5 sacks cement. Shot casing @3210', 3025', 2805', 2680', 2555', 2430', 2310' and pulled a total of 77 joints of pipe. Plugged well with 4 sacks hulls, 15 sacks gel, 75 sacks cement, 1 sack hulls, 10 sacks gel, released plug and displaced with 75 sacks 50/50 pos, 4% gel, 3% cc. Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

MAR 4 1982  
3-4-1982  
CONSERVATION DIVISION  
Wichita, Kansas

(Signature) R. Darrell Kelso  
Box 176 Chase, Kansas 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 19 82



Irene Hoover  
Notary Public.

My Commission expires:

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

15.145-00541.0000


COPY

Company- THUNDERBIRD DRILLING, INC.  
Farm- Van Rensseler No. 1

SEC. 5 T. 20 R. 19W  
SE NE SW

Total Depth. 4290'  
Comm. 2-27-63 Comp. 3-9-63  
Shot or Treated.  
Contractor. Red Tiger Drilling Co.  
Issued. 9-7-63

County . Pawnee  
KANSAS



CASINO:

8 5/8" 352' cem w/200 sx.  
5 1/2" 4290' cem w/100 sx.

K. G. S. LIBRARY

Elevation. 3222.1 DF

Production. 104 BOPD, NW

Figures Indicate Bottom of Formations.

surface	352
shale & redbed	790
sand	1045
redbed & sand	1362
Anhydrite	1400
shale & redbeds	1800
shale	2215
shale & lime	2345
shale	2500
shale & lime	2660
lime	2880
lime & shale	3550
lime	4179
lime & sand	4215
lime & shale	4250
lime	4290
Total Depth	

TOPS: LOG

Heebner	3677
Lansing	3725
Pawnee Sand	4173
Ft. Scott Lime	4187
Cherokee Sand	4202
Mississippi	4274

RECEIVED  
STATE CORPORATION COMMISSION

OCT 15 1961

CONSERVATION DIVISION  
Wichita, Kansas