


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Pawnee County, Sec. 3 Twp. 20 Rge. 18 (E) (W)

Location as "NE/CNW%SW%" or footage from lines SW NE SW  
Lease Owner Westpan Hydrocarbon Company  
Lease Name Clock-Rowe Well No. 1  
Office Address Land Bank Bldg., 15 W. 10th St., Kansas City 6, Missouri.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Nov. 16th 1953  
Application for plugging filed Nov. 16th 1953  
Application for plugging approved Nov. 16th 1953  
Plugging commenced Nov. 16th 1953  
Plugging completed Nov. 16th 1953  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation Depth to top Bottom Total Depth of Well 4075' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	294'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud. Layed down drill pipe, cemented with 20 sacks of cement, at 300', filled surface pipe with mud. Set 10 sacks of cement, plug at 40'.

FILED  
COMMISSION

12-5-1953


Name of Plugging Contractor Sterling Drilling Company  
Address Sterling, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.  
Rollin Mead (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Rollin Mead  
Sterling, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 19th day of November, 1953

My commission expires September 17, 1957 Notary Public.



24-7368-6 3-53-20M

PLUGGING  
FILE SEC 3 T 20 R 18 E  
BOOK PAGE 143 LINE 18

# STERLING DRILLING CO.

STERLING, KANSAS

WELL LOG- ----- -CLOCK-ROWE #1

Location: SW NE SW of Section 3-20-18, Pawnee County, Kansas

OWNER: West Pan Hydrocarbon Company  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company  
CABLE TOOL CONTRACTOR:

Commenced: 10-30-53 (W.r)  
(W.c./t)

Completed: 11-16-53 (W.r)  
(W.c./t)

Total Depth: 4075'

COPY

LOG

0- 305	Shale
305- 480	Shale & Shells
480- 550	Shale & Sand
550- 870	Shale
870-1250	Red Bed & Shale
1250-1285	Anhydrite
1285-1520	Shale & Shells
1520-1960	Shale
1960-2110	Shale & Lime
2110-2860	Lime
2860-2990	Shale
2990-3110	Lime
3110-3300	Lime & Shale
3300-3925	Lime
3925-3970	Lime & Shale
3970-3983	Core #1
3983-3995	Core #2
3995-4010	Core #3
4010-4019	Core #4
4019-4027	Core #5
4027-4075'	Lime

CASING RECORD

Ran 294' of 8-5/8" casing, cemented with 175 sacks of bulk cement.

PRODUCTION

Dry and abandoned

**PLUGGING**  
 FILE SEC 3 T 20 R 18  
 BOOK PAGE 143 LINE 18

STATE OF KANSAS  
 DIVISION OF OIL AND GAS