


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Return to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barton County. Sec. 15 Twp. 20 Rge. 13 (XX W(W))

Location as "NE/CNWSW" or footage from lines NE NE NE  
Lease Owner Woodman & Iannitti Drilling Co.  
Lease Name Voight Well No. 1  
Office Address Box 387, Hoisington, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 3-14 1957  
Application for plugging filed 3-13 1957  
Application for plugging approved 3-13 1957  
Plugging commenced 3-14 1957  
Plugging completed 3-14 1957  
Reason for abandonment of well or producing formation Dry.

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well R. M. Brundege  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3524 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	210'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud, 1/3 sack of hulls. Bottom plug 200', 20 sacks of cement, 1/3 sack of hulls. Top plug 25', 5 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Woodman & Iannitti Drilling Co.  
Address P. O. Box 387, Hoisington, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
K. T. Woodman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. T. Woodman  
717 Union Nat'l. Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of March, 1957

RECEIVED  
STATE CORPORATION COMMISSION  
Lucille J. Livingston  
Notary Public.

My commission expires November 30, 1959

MAR 15 1957  
CONSERVATION DIVISION  
Wichita, Kansas  
3-15-1957

PLUGGING  
FILE SEC. 15 T. 20 R. 13w  
BOOK PAGE 148 LINE 29

DRILLING LOG

Company: Woodman & Iannitti and Brown & Fortier  
 Well: #1 Voight NE NE NE 15-20-13, Barton County, Kansas  
 Contractor: Woodman & Iannitti Drilling Co.  
 P. O. Box 387, Hoisington, Kansas  
 Date Comm: 3-4-57  
 Date Compl: 3-14-57  
 T. D. 3524'  
 Casing: 8 5/8" at 210'

Figures Indicate the Bottom of Formation

0-85	Sand	2365	Shale & Lime Shells
96	Iron	2520	Shale & Shells
117	Pyrite	2640	Shale & Shells
140	Iron Pyrite	2775	Shale & Lime Shells
210	Shale & Shells	2805	Lime & Shale
300	Shale & Shells	2915	Shale & Lime
560	Red Bed & Shale	2980	Lime & Shale
662	Sand & Red Bed	3035	Lime & Shale
711	Red Bed & Shale	3090	Lime
715	Shale	3200	Lime
855	Shale & Shells	3228	Shale & Lime
960	Shale & Red Bed	3270	Lime - L.K.C.
1050	Shale	3330	Lime
1200	Shale & Shells	3365	Lime
1400	Shale	3435	Lime
1635	Shale & Shells	3495	Lime & Cong.
1654	Shale & Shells	3524	Cong. & Arb.
1740	Lime & Shale		
1830	Brown Lime & Shale		
1860	Shale		
1885	Lime & Shale		
1985	Lime & Shale		
2155	Lime & Shale		

GEOLOGICAL TOPS

Elevation	1865 RB
Anhydrite	711 / 1154
Heebner	3096 - 1231
Toronto	3116 - 1251
Brown Lime	3215 - 1350
Lansing	3228 - 1363
Conglomerate	3461 - 1594
Arbuckle	3496 - 1631
Total Depth	3524 - 1659

RECEIVED  
 STATE CORPORATION COMMISSION

MAR 15 1957

CONSERVATION DIVISION  
 Kansas

I certify the above to be a true and correct copy of the Driller's Log and Geological Tops, to the best of my knowledge and belief.

**PLUGGING**  
 FILE SEC 15 T 20 R13W  
 BOOK PAGE 148 LINE 29

WOODMAN & IANNITTI DRILLING CO.

By *K. T. Woodman*  
 K. T. Woodman