

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barton SEC. 27 TWP. 20RGE. 14 N/W
Location as in quarters or footage from lines:
NE NW SW

Locate Well
correctly on above
Section Platt.

Lease Owner Tiger Energy Corporation
Lease Name Kirkman Well No. 1
Office Address 1127 South Lewis Tulsa, OK 74104
Character of Well (Completed as Oil, Gas or Dry Hole):
Date Well Completed 5-19-83
Application for plugging filed 5-19-83
Plugging commenced 5-19-83
Plugging completed 5-19-83
Reason for abandonment of well or producing formation _____

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ bottom T.D. 3620'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out.

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____
feet to _____ feet for each plug set.

Bottom Plug: @ 3540' w/20 sacks 50/50 pozmix, 4% gel 3% cc. thru drill pipe
Next Plug: @ 840' w/20 " " " " " " "
Next Plug: @ 420' w/100 " " " " " " "
Top Plug: @ 40' w/Bridged plug and 10 sacks cement
10 sacks cement in rat hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lobo Drilling Co.

STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors (employee of owner) or (~~owner/oper~~) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Ervin Neighbors
Box 877 Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 27 day of May, 1983

Notary Public
STATE CORPORATION COMMISSION

My Commission expires: 4-29-86

MAY 31 1983

DRILLERS' WELL LOG

DATE COMMENCED: May 13, 1983
DATE COMPLETED: May 19, 1983

Tiger Energy Corp.
KIRKMAN #1
NE NW SW
Sec. 27, T20S, R14W
Barton County, Ks.

ELEVATION: 1970 K.B.

0 - 827' Surface Soil, Sand, Red Bed
827 - 858' Anhydrite
858 - 3183' Shale & Lime
3183 - 3187' Shale
3187 - 3206' Lime & Shale
3206 - 3217' Lime
3217 - 3288' Shale
3288 - 3399' Lime & Shale
3399 - 3526' Lime
3526 - 3546' Shale, Lime, Chert, Sand
3546 - 3578' Shale & Sand
3578 - 3620' Dolomite
3620' RTD

FORMATION DATA

Anhydrite 827'
Heebner 3183'
Toronto 3206'
Douglas 3217'
Br. Lime 3288'
Lansing K.C. 3399'
Base K.C. 3526'
Conglomerate 3531'
Simpson Shale 3546'
Arbuckle 3578'
RTD 3620'

Surface Pipe: Set new 8-5/8",
23# pipe @407' w/285 sacks
common 2% gel 3% cc.

AFFIDAVIT

STATE OF KANSAS
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and
statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 27 day of May 1983.

My Comm. Expires:

4-29-86

Quincy M. Hague
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

MAY 31 1983

CONSERVATION DIVISION
Wichita, Kansas