

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

Barton County, Sec. 27 Twp. 20 Rge. 14 (E) (W)

Location as "NE/CNW%SW%" or footage from lines SW SW SE

Lease Owner D. R. Lauck Oil Company, Inc.

Lease Name Russell Well No. 1

Office Address _____

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed April 14, 1953

Application for plugging filed April 14, 1953

Application for plugging approved April 14, 1953

Plugging commenced April 14, 1953

Plugging completed April 14, 1953

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3622 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
sand & shale	water	270	380	8 5/8	576	cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud	3622 -	270
mud plug	270 -	265
20 sax cement	265 -	225
mud	225 -	30
wood plug	30 -	25
cement	25 -	bottom of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D. R. Lauck Oil Company, Inc.

Address 301 South Broadway Wichita 2 Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

James F. Ralstin

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James F. Ralstin

Wichita Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of April, 19 53

My commission expires Sept. 14, 1955

24-2675-B 2-52-20M

APR 20 1953 4-18-1953

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 27T20R
BOOK PAGE 98 LINE 29

15.009.00217.0000

D. R. Lauck Oil Company, Inc. et.al.

Russell #1

SW SW SE Sec.27-20-14W
Barton County Kansas

Commenced April 2, 1953
Completed April 14, 1953

Elevation: 1905 K.B.

576 ft of 8 5/8" casing cemented with 350 sacks D & A

Clay and sand	145
shale & shells	270
sand & Iron	380
sand & shale	520
Red bed	830
Anhydrite	855
shale & red bed	1005
shale & shells	1650
shale & lime	1965
Lime & shale	2055
shale & lime	2200
Lime & shale	2306
shale & lime	2835
Lime	3255
sand & shale	3315
lime	3622

DST #1	3222-3287 Packer failed
DST #2	3217-3287 Packer failed
DST #3	3302-3319 Open 30" rec.1100' salt water BHP 1240#
DST #4	3585-3622 Open 30" rec.215' muddy salt water BHP 1120#

Tops	
Heebner	3194
Brown Lime	3298
Lansing	3308
Conglomerate	3553
Arbuckle	3581
T D	3622

PLUGGING
FILE SEC. 27 T. 20 R. 14 W.
BOOK PAGE 93 LINE 29

The Above is a true and correct copy of the log of Russell #1, to the best of my knowledge and belief.

Dated at Wichita, Kansas, this 16th day of April, 1953.

James F. Ralstin
James F. Ralstin

STATE OF KANSAS
CONSERVATION DIVISION
Wichita, Kansas

APR 13 1953 Subscribed and sworn to before me this 16th day of April, 1953.

Elizabeth Gay
Notary Public

My commission expires: Sept. 14, 1955