


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211-N. Broadway
Wichita, Kansas

Rice County. Sec. 5 Twp. 20S Rge. (E) 8 (W)
Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner Kewanee Oil Company
Lease Name Koons Well No. 2
Office Address P. O. Box 360, Hoisington, Kansas 67544
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 20, 19 65
Application for plugging filed February 21, 19 65
Application for plugging approved Verbal February 21, 19 65
Plugging commenced February 21, 19 65
Plugging completed February 21, 19 65
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - Verbal from Mr. Gilbert Toman

Name of Conservation Agent who supervised plugging of this well Mr. Gilbert Toman
Producing formation Dry Hole Depth to top Bottom 3350 Total Depth of Well 3350 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	Dry	2702		8-5/8"	207	None
Toronto	Dry	2725				
Douglas	Dry	2734				
Br. Lime	Dry	2841				
Lansing K.C.	Dry	2877				
Upper Kinderhook	Dry	3228				
Lower Kinderhook	Dry	3259				
Maquoketa	Dry	3321				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 195'. Set plug of 1/2 sack hulls and 25 sacks cement.
Filled hole with mud to 40'. Set plug of 1/2 sack hulls and filled pipe to surface with 10 sacks cement. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 3 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert-Jones Drilling Company
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Paul G. Arnold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul G. Arnold
P. O. Box 360, Hoisington, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of March, 19 65

My commission expires 8-2-65 Notary Public.



GABBERT-JONES INC.
WICHITA, KANSAS
DRILLERS WELL LOG

KOONS #2
 SW SW SW SECTION 5-20S-8W
 RICE COUNTY, KANSAS

COMMENCED: FEBRUARY 13, 1965
 COMPLETED: FEBRUARY 21, 1965

OPERATOR - KEWANEE OIL COMPANY

DEPTH	FORMATION	REMARKS
FROM To		
0 100	SURFACE CLAY & SAND	
100 207	SHALE	RAN 7 JOINTS 8-5/8" CASING, SET @ 207' w/200 SACKS CEMENT
207 230	RED BED	
230 244	ANHYDRITE	
244 560	SHALE	
560 1440	SHALE & LIME	
1440 1520	LIME	
1520 1695	SHALE & LIME	
1695 2100	LIME	
2100 2503	SHALE & LIME	
2503 2620	SHALE	
2620 2780	SHALE & LIME	
2780 2840	SHALE	
2840 2898	SHALE & LIME	
2898 3232	LIME	
3232 3269	SHALE	
3269 3282	SHALE & SAND	
3282 3350	SHALE	
3350 TD		DRY & ABANDONED

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 3 1965
 CONSERVATION DIVISION
 Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN THE SW SW SW SECTION 5-20S-8W, RICE COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 23RD DAY OF FEBRUARY, 1965, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
 BARBARA J. LAYTON, NOTARY PUBLIC

MY COMMISSION EXPIRES FEBRUARY 1, 1968