


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rice County. Sec. 4 Twp. 20S Rge. 8W (X) (W)
Location as "NE/CNW/SW" or footage from lines Approx C S/2 S/2 SW/4
Lease Owner Ben C. W. Hyde, Jr.
Lease Name HABIGER Well No. 1
Office Address 4722 Broadway
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 7 1966
Application for plugging filed December 7 1966
Application for plugging approved December 7 1966
Plugging commenced December 7 1966
Plugging completed December 7 1966
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3585 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
shale & shells		246	795	8 5/8	246	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug at 240' with 25 sacks cement and 1/4 sacks hulls.
Top plug at 40' with 10 sacks cement and 1/2 sack hulls.
Two sacks in Rat Hole

RECEIVED
STATE CORPORATION COMMISSION

DEC 9 1966

12-9-1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Isern Drilling Company
Address Box 486, Ellinwood, Ka as 67526

STATE OF KANSAS, COUNTY OF BARTON, ss.
W. F. Banks (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. F. Banks
Box 486, Ellinwood, Kansas 67526
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of December, 1966.

My commission expires February 10, 1967.

George A. Meyer
George A. Meyer Notary Public.

W E L L L O G

HYDE, ISERN-WELLS, HABIGER #1
Approx C S/2 S/2 SW/4
Section 4-20S-8W
Rice County, Kansas

Figures indicate bottom of formation:

ELEVATION: 1671' KB

ROTARY COMMENCED: 11-29-66
ROTARY COMPLETED: 12-7 -66

PIPE RECORD:
8 5/8" set @ 246'
with 225 sacks cement.

0	to	10	cellar
		30	clay
		80	sand
		100	shale
		243	red bed
		1065	shale & shells
		1600	lime & shale
		2430	shale & shells
		2765	lime & shale
		2860	shale
		3260	lime & shale
		3323	shale & lime
		3370	lime
		3407	shale & lime
		3414	sand
		3515	lime & shale
		3529	sand
		3555	sand, lime & shale
		3585	lime & shale
		3585	Rotary Total Depth

TOPS

Heebner	2722
Brown Lime	2863
Lansing	2900
Kinderhook Lime	3326
Kinderhook Sand	3410
Maquoketa	3436
Viola	3474
Simpson Sand	3523
Arbuckle	3582

RECEIVED
STATE CORPORATION COMMISSION

DEC 9 1966


STATE OF KANSAS)
COUNTY OF BARTON) ss

CONSERVATION DIVISION
Wichita, Kansas

I, Dean Wells, Partner of Isern Drilling Company, contractor for the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matter herein contained pertaining to the log of the above-described well, as filed and that the same are true and correct.


Dean Wells, Partner

Subscribed and sworn to before me on this 8th day of December, 1966.


George A. Meyer, Notary Public

My commission expires Feb. 10, 1967.