


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rice County, Sec. 6 Twp. 20 Rge. 8 (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner Specter Pipe & Supply Co.
Lease Name Richardson-Smith Well No. 1
Office Address Box 169 Russell, Kans. 67665
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 9-25-64 19
Application for plugging filed Oct. 20, 1973 19
Application for plugging approved Oct. 23, 1973 19
Plugging commenced 10/24 19 73
Plugging completed 10/27 19 73
Reason for abandonment of well or producing formation failure to produce
profitably
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Maquoketa Depth to top 3324 Bottom 3341 Total Depth of Well 3342 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	OD 215ft	none
				4 1/2"		2403'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug at 2900'. Sand & 3 sacks cement from 2900' to 2870'.

Pumped 2 sacks hulls, 20 sacks gel mud, 1 sack hulls & 85 sacks cement to plug well.

RECEIVED
STATE CORPORATION COMMISSION
NOV 12 1973
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Glenn's Pipe Pulling Co.
Address Box 156 Ellinwood, Kansas 67526

STATE OF Kansas, COUNTY OF Russell, ss.
Specter Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Glenn Specter

(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of November, 1973

Wilma M. Lindahl

My commission expires May 21, 1975

Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15 159.30484 0000


COPY

Company- CHAMPLIN OIL & REF.
Farm-Richardson-smith No. 1

SEC. 6 T. 20 R. 8W
SE SE SE

Total Depth. 3342
Comm. 9-19-64 Comp. 9-25-64
Shot or Treated.
Contractor. Red Tiger Drlg..
Issued. 11-28-64

County Rice KANSAS



CASING:
8 5/8" 215.06' 175 sx.cem.

Elevation. 1675DF

Production. Dry

Figures Indicate Bottom of Formations.

surface soil & clay	20
sand & shale	70
shale	140
redbed	239
Anhydrite	241
redbed	245
Anhydrite	258
shale & shells	980
shale & salt	1065
lime & shale	2665
lime	2720
shale	2724
lime	2729
lime & shale	2753
Douglas	2858
lime	3105
chert & lime	3120
lime	3245
conglomerate	3342RTD

SCOUT TOPS:

Heebner	2720
Brown Lime	2857
Lansing	2894
Base Kansas City	3180
Conglomerate	3197
Kinderhook	3230
1st. Kinderhook sd.	3239-41
2nd. Kinderhook sd.	3259-61
Kinderhook shale	3287
Maquoketa	3324

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1973
CONSERVATION DIVISION
Wichita, Kansas