


STATE OF KANSAS CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Rice County, Sec. 6 Twp. 20S Rge. 8W (W)

Location as "NE/CNW/SW" or footage from lines NW NE NW

Lease Owner ISERN-WELLS, R. D. Holliday

Lease Name HABIGER Well No. 1

Office Address Box 486, Ellinwood, Kansas 67526

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 21 1968

Application for plugging filed April 25 1968

Application for plugging approved April 21 1968

Plugging commenced April 21 1968

Plugging completed April 21 1968

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3465 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Red Bed		90	220	8 5/8"	217	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 210'; 1/4 sack hulls, plug

25 sacks cement down drillpipe with pump truck.

Filled hole with mud to 40'; 1/4 sacks hulls, plug

10 sacks cement.

Two sacks in Rat Hole

RECEIVED  
STATE CORPORATION COMMISSION  
APR 26 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor ISERN DRILLING COMPANY  
Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS, COUNTY OF BARTON, ss.  
W. F. Banks (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. F. Banks

Box 486, Ellinwood, Kansas 67526 (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of April 1968

My commission expires February 10, 1971

George A. Meyer Notary Public

W E L L L O G

ISERN-WELLS and  
R. D. Holliday, HABIGER #1  
NW NE NW, Section 6-20S-8W  
Rice County, Kansas

ELEVATION: 1681' GL; 1683' DF; 1685' KB.

Figures indicate bottom of formation:

PIPE RECORD:

3 5/8" set at 217'  
with 185 sacks cement.

0	to	30	surface soil & clay
		90	shale with sand
		240	red bed
		1460	shale & shells
		1725	lime & shale
		2010	shale & lime
		2394	shale & shells
		2437	sand
		2730	lime & shale
		2925	shale & lime
		3355	lime & shale
		3420	lime & shale with sand
		3425	lime & shale
		3465	shale & lime
		3465	Rotary Total Depth

ROTARY COMMENCED: 4-15-68  
ROTARY COMPLETED: 4-21-68

LOG TOPS

Anhydrite	240
Heebner	2721
Brown Lime	2856
Lansing	2892
Chert Conglomerate	3200
Kinderhook Sand	3222
Maquoketa	3292
Viola	3340
Simpson Shale	3392
Simpson Sand	3401
Arbuckle	3442
Log Total Depth	3468

RECEIVED  
STATE CORPORATION COMMISSION  
APR 26 1968  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
COUNTY OF BARTON ) ss

I, W. F. Banks, Drilling Superintendent of Isern Drilling Company, contractor for the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matter herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

W. F. Banks  
W. F. Banks

Subscribed and sworn to before me on this 25th day of April, 1968

My commission expires: 2-10-71

George A. Meyer  
George A. Meyer, Notary Public