

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

Rice County, Sec. 18 Twp. 20 Rge. (E) 8 (W)

Location as "NE/CNW/SW" or footage from lines Approx. C NW NW
Lease Owner Frank J. Black
Lease Name Speck Well No. 3
Office Address Box 150, McPherson, Kansas 67460
Character of Well (completed as Oil, Gas or Dry Hole) Input
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced September 18 19 73
Plugging completed May 15 19 74
Reason for abandonment of well or producing formation no longer needed



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3355 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----------|--------|----------|------------|
| | | 0 | 214' | 8 5/8" | 214' | none |
| | | | 333 1/4' | 4 1/2" | 333 1/4' | 2810.19 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3300' and dumped 4 sacks of cement.
Allied Cementing Company plugged well pumping in 3 sacks of hulls, 20 sacks of gel and 85 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS, COUNTY OF BARTON, ss.
Evelyn Roth (employee of owner) or (owner-or-operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of May 19 74

My commission expires Feb. 10, 1975
George A. Meyer
Notary Public.

15.159.02618.0000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- CHAMPLIN OIL & REFINING CO.
Farm- John M Speck No. 3

SEC. 18 T. 20 R. 8W
APPROX. 22NW NW

Total Depth. 3355'
Comm. 6-25-64 Comp. 7-1-64
Shot or Treated.
Contractor. Red Tiger Drilling Co.
Issued. 10-24-64

County Rice
KANSAS



Elevation. 1663' DF

Production. 159 BOPD, NW

CASING:
8 5/8" 214' cem w/175 sx.
4 1/2" 3334' cem w/75 sx.

Figures Indicate Bottom of Formations.

| | |
|----------------------|----------|
| surface | 65 |
| sand & shale | 146 |
| redbed & shale | 216 |
| redbed | 220 |
| Anhydrite | 240 |
| redbed & shale | 450 |
| shale & shells | 1042 |
| lime & shells | 1090 |
| lime | 1510 |
| shale, lime & shells | 1800 |
| shale & shells | 2195 |
| lime w/shale | 2405 |
| lime | 2655 |
| lime & shale | 2721 |
| Heebner | 2726 |
| lime & shale | 2854 |
| Brown Lime | 2885 |
| lime | 3204 |
| chert & lime | 3265 |
| chert, lime & shale | 3355 RTD |
| Total Depth | |

| | |
|-----------------------|------|
| TOPS: LOG | |
| Heebner | 2722 |
| Brown LS | 2855 |
| Lansing Kansas City | 2890 |
| Base Kansas City | 3178 |
| Conglomerate | 3198 |
| Kinderhook Sand | 3242 |
| Cherty Sand | 3251 |
| Lower Maquoketa Shale | 3297 |
| Maquoketa | 3333 |

RECEIVED
STATE CORPORATION COMMISSION
AUG 13 1973
CONSERVATION DIVISION
Wichita, Kansas