

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

R

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 009 - 21674.0000 (of this well)

Operator's Full Name Brougher Oil, Inc.

Complete Address Drawer 1367 Great Bend, Kansas 67530

Lease Name Whorton-Cook Well No. 1

Location 100' S of NE NW SE Sec. 14 Twp. 20 Rge. 14 ~~XXX~~ (W) X

County Barton Total Depth 3540'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 1:30 PM Day 7 Month 11 Year 1979

The above well was plugged as follows:

Sanded back to 3475' and 4 sx cement with dump bailer.

Squeezed thru 8 5/8" surface casing with 4 sx hulls,

s5 sx mud gel, 25 sx cement, 1 sx hulls, 5 sx mud gel,

plug, and 100 sx cement.

Max. pres. 1100#. Shut in pres. 500#.

Recovered approx. 2900' of 4 1/2" casing.

3539' of 4 1/2" casing cemented with 125 sx cement.

792' of 8 5/8" surface casing cement circ.

RECEIVED
STATE CORPORATION COMMISSION

NOV 09 1979
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11-9-79

INV. NO. 08650865-w

Signed: Dwain Rankin
Well Plugging Supervisor