

9

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 29 1964

CONSERVATION DIVISION
Wichita, Kansas

9-29-1964

Operator's Full Name Champlin Oil & Refining Company

Complete Address: P.O. Box 308, Ellinwood, Kansas

Lease Name Richardson-Smith Well No. 1

Location SE SE SE Sec. 6 Twp. 20 Rge. 8 (E) (W)X

County Rice Total Depth 3350'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Red Tiger Drilling Co.

Address: 1723 Wichita Plaza, Wichita, Kansas License No.

Operation Completed: Hour 7:30 AM Day 25 Month September Year 1964

The Above well was plugged as follows:

Hole filled with mud to 200'. Plug and 1/4 sack hulls pushed to 200' and
20 sacks cement pumped through drill pipe. (mud level must have been
correct, as plug and cement went on down hole.) Hole filled with mud
to 200'. Plug and 1/4 sack hulls pushed to 200' and hole cemented with
20 sacks pumped through drill pipe (Haliburton). Hole filled with mud
to 40'. Plug and 1/4 sack hulls pushed to 40' and hole cemented to base
of cellar with 10 sacks. Rathole bridged, and cemented with 2 sacks.

INVOICED I hereby certify that the above well was plugged as herein stated.

DATE 9/30/64
INV. NO. 9899-u

Signed: [Signature]
Well Plugging Supervisor