

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

NOV 4 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Earl Morgan of Sholom Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Icer Addis guarantees payment of the plugging fee.

Operator's full Name: Addis Oil Operations

Complete Address: Box 519, Great Bend, Kansas

Lease Name: Russell Well No. # 2

Location: SE SW SW Sec. 27 Twp. 20 Rge. 14 (E) (W)

County Barton Total Depth 3577 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Earl Morgan was instructed to plug the well as follows:

8 5/8" 631' Cwc. wh/400 sx.

Filled hole with heavy mud to 625'; set plug wh 1/4 sx
hulls; displaced 25 sx cement thru drill pipe. Mud to 300';
set plug wh/ 1/4 sx hulls; displaced 20 sx cement thru
drill pipe. Mud to 40'; 1/2 sx hulls, plug, & displaced
15 sx cement, cementing to base of cellar.

Very truly yours,

John Truman
 Conservation Division Agent