

State of Kansas



15.159.20019.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
MARCH 25, 1967
STATE CORPORATION COMMISSION
MAR 28 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bill Banks of Isern Drilling Company has this

date requested permission to plug the following described well:

Mr. Banks guarantees payment of the plugging fee.

Operator's full Name: Ben C. W. Hyde, Jr. and Isern Drilling Co.

Complete Address: 4722 Broadway, Kansas City, Missouri

Lease Name: Ebright Well No. 1

Location: SE SE SE Sec. 5 Twp. 20 Rge. 8 (E) (W) X

County Rice Total Depth 3545' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Banks was instructed to plug the well as follows:

Fill hole with mud to 225'. Push plug and 1/4 sack hulls to 225' and
cement hole with 25 sacks through drill pipe. Fill hole with mud to
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

[Signature]
Conservation Division Agent