

State of Kansas



15.159.30304.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

December 7, 1966

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bill Banks of Isern Drilling Company has this date requested permission to plug the following described well:

Mr. Banks guarantees payment of the plugging fee.

Operator's full Name: Ben C. W. Hyde, Jr. and Isern-Wells

Complete Address: 4722 Broadway, Kansas City, Missouri

Lease Name: Habiger Well No. 1

Location: C S/2 S/2 SW Sec. 4 Twp. 20 Rge. 8 (E) (W) X

County Rice Total Depth 3585' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Banks was instructed to plug the well as follows:

Fill hole with mud to 240'. Push plug and 1/4 sack hulls to 240' and  
cement hole with 25 sacks through drill pipe. Fill hole with mud to  
40'. Push plug and 1/4 sack hulls to 40' and cap hole with 10 sacks  
cement. Bridge rathole, and cement with 2 sacks.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 9 1966

CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,

William J. Roman  
Conservation Division Agent